

159  
R

4-050135

S-16

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-22,674 00-00

SW SE SW /4 SEC. 19 , 06 S , 25 W  
330 feet from S section line  
3780 feet from E section line

Operator license# 5030

Lease SELM/LINDENMAN well # 1

Operator: VESS OIL CORPORATION

County GRAHAM

Address: 8100 E. 22ND. ST. N. BLDG 300  
WICHITA, KANSAS 67226  
(316) 682-1537

Well total depth 3860 feet  
Conductor Pipe: \_\_\_\_\_ inch @ \_\_\_\_\_ feet  
Surface pipe 8 5/8 inch @ 297 feet

125.45

Aband. oil well \_\_\_\_\_, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A

Plugging contractor: L.D. DRILLING INC. License# 6039

Address: \_\_\_\_\_

Company to plug at: Hour: PM Day: 16 Month: MAY Year: 1992

Plugging proposal received from: GREG DAVIDSON

Company: L. D. DRILLING INC. phone: \_\_\_\_\_

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ <u>2185</u> feet with	25	sacks	Rat hole: <u>15</u> sacks
2nd plug @ <u>1420</u> feet "	100	"	
3rd plug @ <u>345</u> feet "	40	"	
4th plug @ <u>40</u> feet "	10	"	with 8 5/8" wiper plug

Plugging Proposal Received by: Marvin L. Miller

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 3:45 PM , Day: 16 , Month: MAY , Year: 1992

Actual plugging report: Hole reported plugged as above.  
Order 190 sx 60/40 pozmix w/ 6% gel and 1/4# celloflake or flowcel per sk

Remarks: Elevation: 2597, Anhydrite: 2170-2202 feet, Anhydrite plug: 2185  
Bottom plug (in place): Yes  , Calc \_\_\_\_\_ , No \_\_\_\_\_ Arbuckle: NONE

Did NOT penetrate Arbuckle, cemented by ALLIED CEMENTING COMPANY

I did  did not [  ] observe the plugging.

*Marvin L. Miller* RECEIVED  
STATE CORPORATION COMMISSION  
Marvin L. Miller P.I.R.T.II  
(agent) JUN 1 1992  
Form CP-2/3  
CONSERVATION DIVISION  
Wichita, Kansas

6-1-92

**INVOICED**

DATE 6-3-92  
INV. NO. 35378