

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-191-22376-00-00  
Spot: N2SESENE Sec/Twnshp/Rge: 35-34S-2E  
2200 feet from N Section Line, 330 feet from E Section Line  
Lease Name: MCCORGARY-SUNDANCE Well #: 6  
County: SUMNER Total Vertical Depth: 3250 feet

Operator License No.: 30253  
Op Name: CYCLONE PETROLEUM, INCORPORAT  
Address: 7030-C S. LEWIS ST., STE 541  
TULSA, OK 74136

CIBP Size: feet: 3020  
CIBP Size: feet: 3125  
PROD Size: 4.5 feet: 3241 125 SX CMT CLASS A  
SURF Size: 8.625 feet: 265 150 SX CMT CLASS A

#105<sup>63</sup>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/28/2005 8:00 AM  
Plug Co. License No.: 3954 Plug Co. Name: JAED PRODUCTION CO., INC.  
Proposal Rcvd. from: JAMES HAVER Company: CYCLONE PETROLEUM, INC. Phone: (918) 291-3200

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: PARTIAL  
Date/Time Plugging Completed: 03/28/2005 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Sanded back to 2400' with 6 sacks of cement on top of sand. Shot off casing at 2200' and pulled to surface. Ran 2" tubing to 325' and circulated cement to surface with 108 sacks of 60/40 posmix with 4% gel.

Consolidated Service #3550

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 3140 | 3146 |      |          |
| 3068 | 3072 |      |          |
| 2808 | 2810 |      |          |

RECEIVED  
KCC DISTRICT #2

MAR 30 2005

WICHITA, KS

RECEIVED

APR 13 2005

KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed 

(TECHNICIAN)

INVOICED

4-13-05

DATE

NO. 2005061407