

4-032185

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

11-13

API Number: 15-065 210/0-00-00

SW NW SW /4 SEC. 32 , 06 , 25 W  
1650 feet from S section line  
4950 feet from E section line

Operator license# 5474

Lease: Jeffery Well # 1

Operator: Northern Lights Oil Co. LD

County: Graham 125.77

Address: P.O. Box 164  
Andover, Kansas 67002

Well total depth 3870 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 290 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Allied Cement Company License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 13 Month: November Year: 1996

Plugging proposal received from: Dale Jewett

Company: Northern Lights Oil Co. LD Phone:

Were: Order 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 21 1996

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 12:15 P.M., Day: 13, Month: November, Year: 1996

Actual plugging report: 8 5/8" set at 290' w/225 sxs. 4 1/2" set at 3870' with 125 sxs. Prod. perfs 3859' - 3862'. Critical control shots at 2177' and 1350'. Sanded back to 3540' with 4 sxs on sand with bailer. Didn't pull pipe. Mixed and pumped 40 sxs cement with 200# hulls, followed with 12 sxs gel, followed with 150 sxs cement with 200# hulls to Max. P.S.I.. 1100# and held. Squeezed 8 5/8" with 50 sxs cement to Max. P.S.I. 600#. Held. Plug complete.

Remarks:  
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING. Elevation: GL

I did/did not observe the plugging.

CONSERVATION DIVISION 11-21-96

Carl Goodrow  
(agent)  
Form CP-2/3

INVOICED  
DATE 11-22-96  
INV. NO. 47035

Handwritten initials