

6 030735

15-065-03250-0000

API NUMBER 15- 1955

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE¹WN⁴SEC. 30, T. 6 S, R. 25

4950 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name TEDRO Well # 1

Operator: JOHN O FARMER

County GRANHAM 126.10

Name & Address BOX 352

Well Total Depth 3880' feet

RUSSELL KANSAS

Conductor Pipe: Size _____ feet

67665

Surface Casing: Size 8 5/8 feet 300'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON RockHold License Number _____

Address OBERLIN KANSAS

Company to plug at: Hour: AM Day: 30 Month: 4 Year: 19 86

Plugging proposal received from SKIM EICHMAN

(company name) JOHN O FARMER (phone) _____

were: 8 5/8 SET @ 300' w/ 150 SX. 5 1/2 SET @ 3879' w/ 125 SX. PERF 3851-3752

POTD 3870' ORDER 180 SX. 60/40 PZ 6 7/8 GEL 3 1/2 40 SX. GEL 5 SX. HULLS

ORDER SAND & CEMENT. PULL PIPE.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:45 AM Day: 30 Month: 4 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND TO 3700' SPOT 5 SX. CEMENT. ON SAND w/ BRILER

PULL PIPE.

TIE ON TO 8 5/8 MIX. & Pump 3 SX. HULLS 23 SX. GEL 100 SX. CEMENT MIX.

17 SX. GEL. 80 SX. CEMENT MIX. MAX. PSI 300* CLOSE IN 150* PLUG. COMP

Remarks: (If additional description is necessary, use BACK of this form.)

observe this plugging.

DATE MAY 16 1986

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 13858

STATE CORPORATION COMMISSION
MAY 16 1986
CONSERVATION DIVISION
WICHITA, KANSAS
5-16-86
25-1986
5-15-86