

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

Rev. 12-4-81
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API NUMBER 15-179-20,573-0000 (of this well)
(This must be listed; if no API# is available, please note drilling completion date.)

LEASE OWNER Kelso Casing Pulling

ADDRESS Box 176 @ Chase, Kansas, 67524 PHONE # (316)-938-2457

LEASE (FARM NAME) Glasgow WELL NO. 1

WELL LOCATION SE SW NW SEC. 21 TWP. 6 S RGE. 26 W (~~East~~)(West)

COUNTY Sheridan TOTAL DEPTH 4020' FIELD NAME _____

OIL WELL GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A _____

WELL LOG ATTACHED WITH THIS APPLICATION AS REQUIRED? yes
(If not, state reason why)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN immediately

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS _____

Darrell Kelso ADDRESS Chase, Kansas

PHONE # (316)-938-2457

PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. _____

ADDRESS Box 176 @ Chase, Kansas, 67524 PHONE # (316)-938-2457

INVOICE COVERING ASSESSMENT FOR PLUGGING THIS WELL SHOULD BE SENT TO:

NAME Kelso Casing Pulling

ADDRESS Box 176 @ Chase, Kansas, 67524 PHONE # (316)-938-2457

AND PAYMENT WILL BE GUARANTEED BY APPLICANT /OR ACTING AGENT.

,80

SIGNED: *Darrell Kelso*
Applicant for Acting Agent

DATE: 2 - 10 - 82

RECEIVED
STATE CORPORATION COMMISSION
FEB 10 1982
CONSERVATION DIVISION
Wichita, Kansas 67202

CONTRACTOR'S WELL LOG

15-179-20573-00-00

OPERATOR:: Tomlinson Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: GLASGOW #1
 LOCATION: SE SW NW, Section 21-6S-26W
 Sheridan County, Kansas
 SPUD DATE: 11/30/80
 COMPLETION DATE: 12/06/80

0	350	Clay, Sand & Shale
350	826	Shale
826	1537	Shale & Sand
1537	2259	Sand & Shale
2259	2292	Anhydrite
2292	2588	Shale
2588	3770	Shale & Lime
3770	4020	Lime
	4020	Rotary Total Depth

Spud hole @ 1:00 p.m., 11/29/80. Drilled @ 386' in a 12 $\frac{1}{4}$ " hole. Ran 9 jts. of a 8 5/8" - 23# (new) casing (tally 377.60) Set @ 384' RTD. Cemented with 325 sx. of common 3% cc, 2% gel. Cement did circulate. Plug was down @ 6:00 p.m., 11/29/80. Drilled Plug @ 4:00 a.m., 11/30/80. Drilling @ 826' Bit #1, 4-11.

T.D. @ 4020'. Drilled 40 more feet after running log and before running pipe. 2 hrs. drilling, 9 $\frac{1}{4}$ hrs. daywork, 12 3/4 hrs. other. Ran 99 jts. of 4 $\frac{1}{4}$ " - 10 $\frac{1}{2}$ # new casing (tally 3994.39) Set @ 3994' G.L. with 125 sx. of 50/50 posmix, 10% salt, 12 $\frac{1}{2}$ # of Gilsonite per sack. Plug was down @ 6:14 p.m., 12/05/80 by Sun Cementing.

SAMPLE TOPS:

Anhydrite 2259'
 B/Anhydrite 2292'

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)


Jack L. Partridge, Assistant Secretary/Treasurer of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the GLASGOW #1, SE SW NW, Section 21-6S-26W, Sheridan, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Asst. Sec./Trea

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 11th day of December, 1980.

Jeanette A. Metheny
 Jeanette A. Metheny, Notary Public



State of Kansas



15-179-20573-00-00

DHN CARLIN
C. LOUX
WNE T. ROY
HILLIP R. DICK
AROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202
February 17, 1982

THIS PERMIT
MAY 17 1982
EXPIRES

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Glasgow (API#15-179-20,573)
Description	SE SW NW
Section	21-6S-26W
County	Sheridan
Total Depth	4020'

Plugging Contractor

Kelso Casing Pulling

Kelso Casing Pulling
Box 176
Chase Kansas 67524

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) days from the above date.

Yours very truly,

DELBERT J. COSTA, Administrator

Mr. Carl Goodrow, Box 189, Penokee, Ks., 67659, (913)674-5593
is hereby assigned to supervise the plugging of the above named well

NOTE; If you are unable to contact District Plugging Agent at his regular number, call TOLL FREE 1-800-362-1358.