

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

15-179-05576-00-00

WELL PLUGGING APPLICATION FORM

Lease Owner Harry Gore Address 400 Brown Building
(Applicant) Wichita, Kansas

Lease (Farm Name) Glasgow Well No. 1

Well Location SW SW NE Sec. 20 Twp. 6 Rge. 26 (E-W)

County Sheridan Field Name (if any) _____

Total Depth 3970 Oil _____ Gas _____ Dry Hole X

Was well log filed with application? Yes ~~No~~. If not, explain: _____

Attached with plugging report

Date and hour plugging is desired to begin February 18, 1953

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired.
(Use an additional sheet if necessary) None

Name of the person on the lease in charge of well for owner _____

Roger Kolter Address Tulsa, Oklahoma

Name of Plugging Contractor The Veeder Supply & Development Co.

Address P. O. Box 201, Cherryvale, Kansas

Invoice covering assessment for plugging this well should be sent to

Harry Gore Address 400 Brown Bldg. Wichita, Kansas

and payment will be guaranteed by applicant.

STATE OF KANSAS
CONSERVATION DIVISION
WICHITA, KANSAS

THE VEEDER SUPPLY & DEVELOPMENT CO.


BY: Floyd H. Field
Applicant or Acting Agent

Date February 27, 1953

PLUGGING
FILE SEC 20 T 6 R 26
BOOK PAGE 80 LINE 12

3-3-53

Veeder Supply & Dev'l. Co.



Cherryvale, Kansas

Drilled for Harry Gore Farm Glascoc No. 1 Depth 3970
 Contractor Veeder Supply & Development Co. Pipe 316.92' of 8 5/8" casing cemented with 200 sacks cement
 Location SW SW Ne Sec. 20 Twp. 6 Range 26W
 Commenced 2-5-53 Completed 2-18-53 County Sheridan State Kansas

Soil clay	0	40	40		
Gray shale	40	135	95		
Sand shale	135	275	140	TOPS:	
Shale	275	940	665	Heebner	3710
Shale shells	940	1355	415	Toronto Line	3734
Hard sand pyrite	1355	1435	80	Lansing KC	3748
Shale shells	1435	1475	40	Base KC	3958
Shale shells iron	1475	1665	190		
Shale iron	1665	1775	110		
Shale shells pyrite	1775	2030	255		
Red bed	2030	2225	195		
Red bed shale	2225	2258	33		
Anhydrite	2258	2295	37		
Shale shells	2295	2800	505		
Lime shale	2800	2885	85		
Shale iron streaks	2885	2955	70		
Shale lime shells	2955	3050	95		
Lime shale	3050	3100	50		
Lime shale iron streaks	3100	3245	145		
Lime shale	3245	3485	240		
Lime shale iron	3485	3590	105		
Lime	3590	3883	293		
Lime shale	3883	3945	62		
Lime	3945	3970	25		

Plugged @ 320' with 15 sacks cement
 Plugged @ 40' with 10 sacks cement

AFFIDAVIT

STATE OF KANSAS)
 Montgomery County) SS

Floyd W. Hild, of lawful age, being duly and solemnly sworn on oath says: I am a resident of Cherryvale, Montgomery County, Kansas, and I hereby know and on oath state that the above drilling log covering the Glascoc #1 Well in Section 20, Township 6, Range 26W, Sheridan County, Kansas, is true and correct.

Further affiant saith not.

THE VEEDER SUPPLY & DEVELOPMENT COMPANY
 BY Floyd W. Hild

Subscribed and sworn to before me this 20th day of February, 1953.

Edna Lawson
 Notary Public

My commission expires July 11, 1956

PLUGGING
 FILE SEC 20 T 6 R 26
 BOOK PAGE 20 LINE 12

RECORDED
 DIVISION
 3-3-53



15-179-05576-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

February 19, 1953

Well No.	1
Lease	Glasgow
Description	SW SW NE 20-6-26W
County	Sheridan
File No.	80-12

Harry Gore
400 Brown Bldg.
Wichita, Kansas

Dear Sir:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 326, Hays, Kansas.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

BY J. P. Roberts
J. P. ROBERTS

cc: DISTRICT PLUGGING SUPERVISOR