

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
245 North Water  
WICHITA, KANSAS 67202

Rev. 6-3-74  
FORM CP-1

WELL PLUGGING APPLICATION FORM  
File One Copy

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 24 1977  
2-24-77  
CONSERVATION DIVISION  
WICHITA, KANSAS

API Number 15-065-20888-0000 (of this well)  
Lease Owner Patrick Petroleum, Inc.  
Address 200 E. First, Suite 414, Wichita, Kansas 67202  
Lease (Farm Name) ELLIOTT Well No. 2  
Well Location SE SW NE Sec. 31 Twp. 6S Rge. XX 23W (W)  
County Graham Total Depth 3950' Field Name \_\_\_\_\_  
Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ Rotary D & A X  
Well Log attached with this application as required Yes  
Date and hour plugging is desired to begin 2:15 a.m. 2-17-77


PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:  
Gerrell Veatch Address 38 Walnut Drive, Hill City, Ks.

Plugging Contractor Abercrombie Drilling, Inc. License No. \_\_\_\_\_  
Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:  
Name Patrick Petroleum, Inc.  
Address 200 E. First St., Suite 414, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed:   
Applicant or Acting Agent  
Jack L. Partridge  
Date: February 22, 1977

CONTRACTOR'S WELL LOG

13-065-20888-00-00

OPERATOR: Patrick Petroleum, Inc.  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: ELLIOTT #2  
 LOCATION: SE SW NE, Section 31-6S-23W  
 Graham County, Kansas  
 SPUD DATE: 2-07-77  
 COMPLETION DATE: 2-17-77

0	275	Clay & Sand
275	1730	Shale
1730	1924	Sand
1924	2156	Shale
2156	2190	Anhydrite
2190	2575	Shale with lime streaks
2575	2752	Shale
2752	3543	Shale & Lime
3543	3784	Lime & Shale
3784	3950	Lime
	3950	Rotary Total Depth

Spud hole at 4:00 p.m. 2-07-77. Cut 306' of 12 1/4" hole. Ran 8 jts. of 8 5/8" casing. (Tally 298') Set at 305' K.B. with 275 sx. 50/50 posmix, 2% gel, 3% Ca. Cl. Plug was down at 10:00 p.m. Cement did circulate.

T.D. 3950'. Set 1st plug at 1100' with 70 sx., 2nd plug at 300' with 20 sx., 40' bridge with 10 sx. Cemented with 50/50 posmix, 6% gel. Plug was down at 2:15 a.m. 2-17-77. State Plugger - Gilbert Balthazor.

SAMPLE TOPS:

Anhydrite 2156' (+331)  
 B/Anhydrite 2190' (+297)

STATE OF KANSAS )  
 )  
 COUNTY OF SEDGWICK )

2-24-77

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the ELLIOTT #2, SE SW NE, Section 31-6S-23W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge  
 Jack L. Partridge, Asst. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 22nd day of February, 1977.

Kathy S. Goertz  
 Kathy S. Goertz, Notary Public



State of Kansas



15-065-20888-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

February 22, 1977

WELL PLUGGING AUTHORITY

Well No.	2
Lease	Elliott
Description	C SE SW NE Sec. 31-6-23W
County	Graham
Total Depth	3950
Plugging Contractor	Abercrombie Drilling, Inc.


Patrick Petroleum Corp.  
200 East First, Suite 414  
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,

  
J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, P.O. Box 9, Route #1, Palco, Kansas 67657  
is hereby assigned to supervise the plugging of the above  
named well.