

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1978
4-24-78
CONSERVATION DIVISION
Wichita, Kansas

API Number 15-065-21011-00-00 (of this well)
Lease Owner F & M Oil Company
Address 505 Union Center, Wichita, Kansas 67202
Lease (Farm Name) Steichen Well No. 2
Well Location NW SW SW Sec. 20 Twp. 6 S Rge. (E) 25 (W)
County Graham Total Depth 3880 Field Name _____
Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin April 19, 1978, 8:00 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Harold Maley Address 216 E. McFarland, Hill City, Ks. 67642

Plugging Contractor Abercrombie Drilling, Inc. License No. _____

Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name F & M Oil Company

Address 505 Union Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: Jack L. Partridge
Applicant or Acting Agent
Jack L. Partridge, Ass't. Sec.-Treas.
Date: April 21, 1978

CONTRACTOR'S WELL LOG

OPERATOR: F & M Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Steichen #2
 LOCATION: NW SW SW Section 20-6S-25W
 Graham County, Kansas
 SPUD DATE: April 8, 1978
 COMPLETION DATE: April 19, 1978

0	315	Sand & shale
315	435	Shale
435	2163	Shale & sand
2163	2198	Anhydrite
2198	2330	Shale
2330	2645	Shale & sand
2645	3428	Shale & lime
3428	3740	Lime & shale
3740	3780	Lime
3780	3799	Lime & shale
3799	3880	Lime
	3880	Rotary Total Depth

Spud at 11:15 a.m., April 8, 1978. Drilled 327' of 12 1/4" hole. Ran 8 joints of 8-5/8" steel casing. Set at 327' with 210 sacks common cement, 3% CaCl, 2% gel. Job complete at 6:30 p.m., April 8, 1978.

3880' T.D. Set 1st plug at 800' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' with 20 sacks, solid bridge, cemented with 50/50 posmix, 6% gel. Plug was down at 8:00 a.m., April 19, 1978. State Plugger - Gilbert Balthazor.

SAMPLE TOPS:

Anhydrite 2163'
 B/Anhydrite 2198'

RECEIVED
 STATE CORPORATION COMMISSION
 APR 24 1978
 42478

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)


CONSERVATION DIVISION
 Wichita, Kansas

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Steichen #2, NW SW SW Section 20-6S-25W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

By Jack L. Partridge
 Jack L. Partridge, Ass't. Sec.-Treas.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state, as of this 21st day of April, 1978.



Sandra Richman
 Sandra Richman, Notary Public

State of Kansas



15-065-21011-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

April 24, 1978

WELL PLUGGING AUTHORITY

Well No.	2
Lease	Steichen
Description	NW SW SW Sec. 20-6-25W
County	Graham
Total Depth	3880
Plugging Contractor	Abercrombie Drilling, Inc.


F & M Oil Co., Inc.
505 Union Center
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, P.O.Box 9, Route #1, Palco, Kansas 67657
is hereby assigned to supervise the plugging of the above named well.