

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API #: 15-017-20861-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date

WELL OPERATOR: American Energies Corporation (owner/company name) KCC LICENSE # 5399 (operator's)

ADDRESS: 155 North Market CITY: Wichita  
STATE: Kansas ZIP CODE: 67202 CONTACT PHONE: 316-263-5785  
LEASE: Stevens WELL#: A #1 Section 18 Township 19S Range 7E  
NE NE SW SPOT LOCATION/QQQQ COUNTY: Chase

2310 S FEET (in exact footage) FROM South LINE OF SECTION (NOT Lease Line)  
2310 W FEET (in exact footage) FROM West LINE OF SECTION (NOT Lease Line)  
KCC - SKA - 4-13-05 - Per RBDMS + Intent.

Check One: Oil Well  Gas Well  D&A  SWD/ENHR WELL  Docket #   
CONDUCTOR CASING SIZE  SET AT  CEMENTED WITH  SACKS  
SURFACE CASING SIZE 7" - 20# SET AT 99' CEMENTED WITH 50 sx SACKS  
PRODUCTION CASING SIZE None SET AT  CEMENTED WITH  SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:  
ELEVATION 1238' G.L.  K.B.  T.D. 1320 PBDT  Anhydrite Depth   
(Stone Corral Formation) JUNK IN HOLE

CONDITION OF WELL: GOOD  POOR  CASING LEAK   
PROPOSED METHOD OF PLUGGING:

Cementing with 119 sx 60/40 poz 4% gel. Ran drill pipe to 250', broke circulation,  
mix and pump 98 sx 60/40 poz with 4% gel to surface. Pulled drill pipe out and topped off with  
21 sx 60/40 poz + 4% gel to surface. Cement stayed in cellar.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? Yes (YES,NO)  
If not explain why? \_\_\_\_\_

**PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.**

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:  
Name: Alan L. DeGood, President Phone#: (316) 263-5785  
Address: 155 North Market, Suite 710 City: Wichita Kansas  
PLUGGING CONTRACTOR: United Cementing (company name) KCC LICENSE #: 30437  
Address: 2510 West 6th Street City: Eldorado State: Kansas Zip 67042

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) 6/4/2004 Plugged  
PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator  Agent

DATE: 03/15/05 AUTHORIZED OPERATOR OR AGENT: Alan L. DeGood  
(signature) Alan L. DeGood, President

RECEIVED  
APR 08 2005  
KCC WICHITA