

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Murfin Drilling Company, Inc. Address: 250 N. Water, Suite 300 Phone: (316) 267-3241 Operator License #: 30606 Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR) The plugging proposal was approved on: 11/3/04 by: Darrell Dipman w/ KCC in Hays, KS (KCC District Agent's Name) Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [] No Producing Formation(s): List All (If needed attach another sheet) 4252-62, 4208-20, 4170-76 Depth to Top: Bottom: T.D.

API Number: 15-12/69-20063-00-00 Lease Name: Texaco Cahoj Unit Well Number: #5 Spot Location (QQQQ): C - SW - SW - 4620 Feet from [X] North / [] South Section Line 660 Feet from [] East / [X] West Section Line Sec. 3 Twp. 1 S. R. 34 [] East [X] West County: Rawlins Date Well Completed: 12/69 Plugging Commenced: 4/8/05 Plugging Completed: 4/8/05

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Surface and Production data.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set. TIH w/tbg to 2480'. RU Swift. Pumped 105 sxs SMD cmt & 450# hulls. Gained circ w/33 bbls. FL was @ 500' FS. Pulled tbg to 1200'. Pumped 50 sxs & 300# hulls. Pulled tbg to 600'. Pumped 50 sx & 250# hulls. Circ cement to pit. TOH w/tbg. Hooked up to 8 5/8". Pumped 10 sxs & press to 150# & held. (Have casing hanger in well). Top off 5 1/2" csg w/60 sxs & csg stayed full. Total cement 275 sxs. Well P&A. Witnessed & approved by Darrell Dipman w/KCC.

Name of Plugging Contractor: Murfin Drilling Company, Inc. License #: 30606 Address: 250 N. Water, Suite 300; Wichita, KS 67202 Name of Party Responsible for Plugging Fees: Murfin Drilling Company, Inc. State of Kansas County, Sedgwick, ss.

RECEIVED APR 19 2005 KCC WICHITA

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature] (Address) 250 N. Water, Suite 300; Wichita, KS 67202 My Commission Expires: 11-04-07

Handwritten signature/initials.