

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

API NUMBER \_\_\_\_\_  
 LEASE NAME Adell Gansing, KC Unit  
 WELL NUMBER 507  
330 Ft. from S Section Line  
2310 Ft. from <sup>W</sup> Section Line  
 SEC. 2 TWP. 6S RGE. 27  or (W)  
 COUNTY Sheridan  
 Date Well Completed 11-24-87  
 Plugging Commenced 2-12-88  
 Plugging Completed 2-12-88

LEASE OPERATOR Coroco, Inc.  
 ADDRESS 3817 NW Expressway, Oklahoma City, OK 73112  
 PHONE# (405) 948-3100 OPERATORS LICENSE NO. 5916  
 Character of Well Oil SWD KCCaB  
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes  
 Which KCC Office did you notify? Carl Goodrow  
 Is ACO-1 filed? No If not, is well log attached? well log sent in with Form CP-1 on 12-16-87  
 Producing Formation Gansing Depth to Top 3677' Bottom 3700' T.D. 3850'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Burlingame</u>	-	<u>3213'</u>	<u>64'</u>	<u>10 3/4"</u>	<u>304'</u>	<u>none</u>
<u>Howard</u>	-	<u>3268'</u>	<u>3310'</u>	<u>5 1/2"</u>	<u>3847'</u>	<u>none</u>
<u>Jopoka</u>	-	<u>3314'</u>	<u>3404'</u>			
<u>Plattsmouth</u>	-	<u>3410'</u>	<u>68'</u>			
<u>Gansing</u>	<u>oil</u>	<u>3677'</u>	<u>3700'</u>			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
RU Halliburton and hooked up to 5 1/2" csg., pumped 150 sks. Conolite w/ 15 sks hulls, pressured up to 600 #, 151P 500#. Hooked up to surface pipe and pumped 100 sks. & conolite cmt @ 200# 151P 150#. Released Halliburton. Cut and capped csg. 5' below ground level. Cleaned and leveled location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5287  
 Address P.O. Box 579, Great Bend, KS 67530  
 STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Kevin L. Vogel, Administrative Supervisor (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Kevin L. Vogel

(Address) 3817 NW Expressway, Oklahoma City, OK 73112

SUBSCRIBED AND SWORN TO before me this 29th day of February, 19 88

Kathy J. Courtney  
 Notary Public

My Commission Expires: 12/23/90