

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-179-0550800-00

API NUMBER 4-31-62

LEASE NAME Ade11

WELL NUMBER 406

125 Ft. from S Section Line

~~1690~~ ⁹⁵⁰ Ft. from W Section Line

SEC. 2 TWP. 6S RGE. 27 XXXX(W)

COUNTY Sheridan

Date Well Completed 4-31-62

Plugging Commenced 1-19-89

Plugging Completed 1-23-89

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Conoco Inc.

ADDRESS 3817 N.W. Expressway, Oklahoma City, OK

PHONE# (405) 948-3100 OPERATORS LICENSE NO. 5916

Character of Well Injection

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-16-88 (date)

by District IV (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Lansing-K.C. Depth to Top 3610 Bottom 3802 T.D. 3853

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS:

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		Surf.	219	8 5/8"	222	0
Lansing - K.C.	Injection	Surf.	3851	5 1/2"	3878	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. RIH w/2 7/8" tbg. & tagged at 2795'. Fluid level was 526'. Pumped 60 sx econolite, 50 sx C1"A" cmt 20 sx econolite. (61.5 bbls. slurry). Pulled 50 jts 2 7/8" tbg. Fluid level was 500' down. Pmpd 26 sx econo. (17 bbls) POOH w/tbg. Filled csg w/8 sx econo. (5 bbls) SIP 150 psi. Pumped 136 sx (87 bbls) down surf pipe, SIP 100 psi. Dumped 1 yd. common cmt dwn csg. Cut & capped csg 4". (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services

Address 600 Colorado Derby Bldg., Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Conoco Inc.

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Chris J. Dodson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Chris J. Dodson

(Address) 3817 N.W. Expressway

SUBSCRIBED AND SWORN TO before me this 15 day of March, 19 89

Candace M. Driscoll
 Notary Public

My Commission Expires: 7/22/92

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 16 1989
 3-16-89
 CONSERVATION DIVISION
 Wichita, Kansas

Detail Cont'd.

BGL & cleaned & restored location. KCC Rep. - Carl Goodrow.

