

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-11203-00-00
Spot: S2NWSW Sec/Twnshp/Rge: 6-22S-13W
1650 feet from S Section Line, 660 feet from W Section Line
Lease Name: G SCHMITT Well #: 1
County: STAFFORD Total Vertical Depth: 3720 feet

Operator License No.: 3942
Op Name: MONROE, ORVILLE DBA BIG "O"
Address: 2820 PASEO DRIVE
GREAT BEND, KS 67530

CIBP Size: feet: 3686
PROD Size: 5.5 feet: 3713 WITH 75 SX CMT
SURF Size: 8.625 feet: 405 WITH 175 SX CMT

#120 90

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/13/2005 3:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 792-2868

Proposed Plugging Method: RIP AT 800' & CIRCULATE TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/13/2005 3:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:


DROVE A HUNG UP 5 1/2" TENSION PACKER TO 1110'. SQUEEZED LKC PERFS OFF EARLIER WITH 100 SX COMMON CMT W/3% CC. DISPLACED DOWN CASING. RIPPED HOLE IN CASING AT 840'. RAN TUBING TO 840'. PUMPED 50 SX CMT - 100# HULLS - 30 SX CMT. CIRCULATING CMT UP 5 1/2". SHUT IN 5 1/2". LOSS CIRCULATION. PUMPED 60 SX CMT WITH 100# HULLS. STILL NO CIRCULATION. PULLED TUBING. WAITED 3 HOURS. FILLED 5 1/2" TO SURFACE WITH 70 SX CMT. PUMPED 15 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. PRESSURED TO 300 PSIG & BLEW HEAD OUT.

RECEIVED
APR 20 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 4-20-05
INV. NO. 2005061436

Form CP-2/3