

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-01340-00-00
Spot: N2NWSW Sec/Twnshp/Rge: 6-22S-13W
2310 feet from S Section Line, 660 feet from W Section Line
Lease Name: G SCHMITT Well #: 2
County: STAFFORD Total Vertical Depth: 3710 feet

Operator License No.: 3942
Op Name: MONROE, ORVILLE DBA BIG "O"
Address: 2820 PASEO DRIVE
GREAT BEND, KS 67530

PROD Size: 5.5 feet: 3703 WITH 150 SX CMT
SURF Size: 10.75 feet: 558 WITH 275 SX CMT

#120⁵⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/11/2005 10:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: RIP @ 800' & CIRCULATE TO SURFACE

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2005 10:25 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3331' & 5 SX CMT. RIPPED A HOLE IN CASING AT 840'. RAN TUBING TO 840'. PUMPED 30 SX CMT. LOSS CIRCULATION. PUMPED 120 SX CMT WITH 150# HULLS . STILL LOSING CIRCULATION. PULL OUT OF HOLE. SDON. 4/12/05; TAGGED CMT AT 950'. RAN TUBING TO 840'. PUMPED 100 SX CMT WITH 250# HULLS MIXED IN. CIRCULATED CMT TO SURFACE UP 5 1/2". PULLED TUBING TOPPED OFF 5 1/2" WITH 10 SX CMT. PUMPED 110 SX CMT DOWN 10 3/4" X 5 1/2". MAXIMUM PRESSURE 350 PSIG. SHUT IN PRESSURE 300 PSIG.

Perfs:


Top	Bot	Thru	Comments
3703	3710	OH	
3528	3535		
3508	3513		
3457	3465		

RECEIVED
APR 20 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: TBG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED
DATE 4.20.05
TRF. NO. 2005061436

Form CR-2/3