

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-19073-00-00
Spot: NENENW Sec/Twnshp/Rge: 9-21S-11W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: MANNING A Well #: 1-9
County: STAFFORD Total Vertical Depth: 3427 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL, SUITE 100
WICHITA, KS 67206

PROD Size: 5.5 feet: 3427 WITH 90 SX CMT
SURF Size: 8.625 feet: 377 WITH 190 SX CMT

A 111 38

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2005 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 3340' & 5 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: PARTIAL
Date/Time Plugging Completed: 04/12/2005 10:45 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

ANHYDRITE @ 536'. SANDED TO 3330' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3398	3401		

RECEIVED
APR 20 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2450' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE

4-20-05

INV. NO.

2005061434

Form CR-213