

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20533-00-00
Spot: NESWSE Sec/Twnshp/Rge: 22-21S-12W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: ROSE Well #: 9
County: STAFFORD Total Vertical Depth: 3654 feet

Operator License No.: 5430
Op Name: ENERGY THREE, INC.
Address: 1437 OLD SQUARE RD #201A
JACKSON, MS 39211

PROD Size: 5.5 feet: 3654 WITH 100 SX CMT
SURF Size: 8.625 feet: 250 WITH 175 SX CMT

#118⁷⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/14/2005 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 3290' & 5 SX CMT. PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/13/2005 11:50 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

ANHYDRITE @ 660'. SANDED TO 3290' & 5 SX CMT WITH DUMP BAILER.
SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 660' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3614	3622		
3442	3444		
3418	3422		
3411	3416		
3340	3344		

RECEIVED
APR 20 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1820' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed Richard W. Lacey

(TECHNICIAN)

INVOICED

DATE 4-20-05

NO. 2005061433

Form CP-21