

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-05511-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 2-6S-27W
4290 feet from S Section Line, 2300 feet from E Section Line
Lease/Unit Name: ADELL LKC Well Number: 807
County: SHERIDAN Total Vertical Depth: 3878 feet

Operator License No.: 6113
Op Name: LANDMARK RESOURCES, INC.
Address: 1616 S. VOSS, SUITE 150
HOUSTON, TX 77056

Conductor Pipe: Size feet: 3126.04
Surface Casing: Size 8.625 feet: 184 200 SX CMT
Production: Size 5.5 feet: 3877 450 SX CMT
Liner: Size feet:

Well Type: EOR UIC Docket No: E08906.7 Date/Time to Plug: 12/12/2001 8:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: CHARLES SCHMIDT Company: LANDMARK RESOURCES, INC. Phone: (316) 755-3523

Proposed Plugging Method: Order 470 sxs 60/40 pozmix and 10% gel.
Order retainer, stinger and work string.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/12/2001 11:30 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 184' w/200 sxs cwc. 5 1/2" set at 3877' w/450 sxs cwc.
PBSD 3843'. Prod. Perfs 3608' - 3798'.
Ran tubing.
Set retainer at 3497'. Mixed and pumped 150 sxs cement blend through stinger to Max. P.S.I. 1000#.
Withdrew stinger and displaced 120 sxs cement blend.
Pulled tubing to 1700' and displaced 120 sxs cement to surface.
Laid down tubing and topped off with 10 sxs cement.
Bad casing.
Plug complete.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Carl Goodrow
(TECHNICIAN)

KCC

RECEIVED

INVOICED

Form CP-2/3
DEC 26 2001

DEC 28 2001

DATE 12-31-01

DEC 19 2001

KCC WICHITA

NO. 2002061103

HAYS, KS

CONTINENTAL OIL CO #807 ADELL~L-KC UT 2-6-27W APP NW SW NE

Contr. BARNETT DRL SHERIDAN County

E 2587RB Comm. 6/27 Comp. 7/19/62 IP INJECTION WELL

| LOG Tops | Depth | Datum | Casing |
|----------|-------|-------|-------------------------------|
| | | | 8" 184/200 SX |
| HEEB | 3565 | -978 | 5" 3877/225 SX |
| | | | PERF (LANS) 4/3608-09: |
| TOR | 3592 | -1005 | 4/3639-40: 4/3652-53: |
| | | | 4/3761-62: 4/3779-80: |
| LANS | 3606 | -1019 | 3797-98: ACID 900: WATER INJ. |
| | | | RATE SATISFACTORY |
| | | | |
| | | | |
| | | | |
| | | | |
| TD | 3878 | -1291 | |

ADELL

| | | |
|---|---|---|
| + | + | + |
| + | + | + |
| + | + | + |

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS