

6 031034

2-2-88 15-179-05283-00-01

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1947

SE SE SW, SEC. 2, T 6 S, R 27 W/E

330 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5916

Lease Name ADELL LKC UNIT Well # 507

Operator: Conoco, Inc.

County Sheridan 125.13

Name & Address 3817 N W Expressway

Well Total Depth 3850 feet

Oklahoma City, Oklahoma 73112

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 304

Abandoned Oil Well Gas Well Input Well SWD Well KCCO/B U&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number -

Address Oberlin, Kansas

Company to plug at: Hour: PM Day: 12 Month: 2 Year: 19 88

Plugging proposal received from David Lorenzo

(company name) Conoco (phone)

were: 10 3/4 set at 304' with 300 sx CWC. 5 1/2 set at 3847' with 300 sx.

cement log top at 700' from perfs at 1923' - 1945' PBTD 3816'

Perfs 3592' - 3789', Order 250 sx econolite 65/35 poz 10% gel 2% dicel

cement blend 5 sx hulls, Halliburton Cmt. Co. LaRue Water Trucks

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:30 PM Day: 12 Month: 2 Year: 19 88

ACTUAL PLUGGING REPORT Squeeze backside with 100 sx to Max PSI 300 #

Close in 150 #

Squeeze 5 1/2 with 150 sx cement blend with 5 sx hulls mixed in.

To Max PSI 500 # close in PSI 150# Plug complete.

Remarks: (If additional description is necessary, use BACK of form)

observe this plugging.

INVOICED

DATE 2-26-88

INV. NO. 19916

2-25-88

Signed Carl Goodrow (TECHN) Carl Goodrow

6-031034 Well evidently 592d between 1923' & 700' OK JHB