

15-179-05291-00 00

*CANCELED*

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
500 INSURANCE BUILDING  
212 NORTH MARKET  
WICHITA 2, KANSAS

Form CP-1

**RECEIVED**  
STATE CORPORATION COMMISSION

OCT 11 1965

WELL PLUGGING APPLICATION FORM  
File One Copy

Lease Owner Continental Oil Company  
(Applicant) Box 267  
Address Great Bend, Kansas 67530

CONSERVATION DIVISION  
WICHITA, KANSAS

Lease (Farm Name) Adell Lansing-KC Unit Well No. 702

1650' FN and NE SW NW  
Well Location 990' FW lines of Sec. 2 Twp. 6S Rge. 27 ~~(E)~~ (W)

County Sheridan Field Name (If any) Adell

Total Depth 3793' Oil Well  Gas Well  Input Well  SWD Well  D & A

Was well log filed with application? Yes If not, explain: \_\_\_\_\_

Your plugging agent will be contacted  
Date and hour plugging is desired to begin prior to plugging operations.

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of the person on the lease in charge of well owner \_\_\_\_\_

Mr. W. B. Huebner Address Plainville, Kansas

Plugging Contractor Unknown License No. \_\_\_\_\_

Address \_\_\_\_\_

Invoice covering assessment for plugging this well should be sent to \_\_\_\_\_

Mr. L. E. Powell Address Box 267, Great Bend, Kansas

and payment will be guaranteed by applicant.

Signed: *L. E. Powell*  
Applicant or Acting Agent

State Corp. Comm.  
File

Date: October 7, 1965

State of Kansas



WM. H. AVERY Governor  
 WILLIAM L. MITCHELL Chairman  
 JAMES O. GREENLEAF Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

October 11, 1965

WELL PLUGGING AUTHORITY

Continental Oil Company  
 Box 267  
 Great Bend, Kansas


Well No.	702 (Boutz # 2)
Lease	Adell Lensing-KC Unit
Description	NE SW NW 2-6-27W
County	Sheridan
Total Depth	3793'
Plugging Contractor	Unknown

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Very truly yours,

  
 J. P. Roberts, Administrator

Mr. W. L. Nichols Morland, Kansas  
 is hereby assigned to supervise the plugging of the above  
 named well.

WELL RECORD

OCT 11 1965

B. H. Boutz No. 2

Date Spudded: July 6, 1945  
Drilling Completed: July 23, 1945  
Date Tested: October 1, 1945

Loc: 990'N. and 990'E. of W/4  
Corner of Sec. 2, T6S, R27W,  
Sheridan County, Kansas

FROM	TO	FORMATION	FROM	TO	FORMATION
0	46	Surface soil	1843	2063	Shale
46	75	Sand	2063	2250	Shale and shells
75	253	Shale and shells	2250	2892	Broken lime
253	732	Shale	2892	3795	Lime
732	1843	Shale and shells			

Elevation 2546'

Ran 240' of 10 3/4"OD 27# 3 Ga. Armco Spiral Weld casing; set at 238'; cemented with 240 sacks of cement.

Top of Lansing Lime 3547'

Ran 3822'8" of 6"OD 18# SRT H40 Electric Weld casing; ran 6"OD SRT Bakblu male and female float collar and 6"OD SRT Bakblu guide shoe; set at 3792'; cemented with 300 sacks of cement.

Well was drilled to a total depth of 3793' in Lansing Lime.

8-8-45 - Drilled out cement to 3784'. Ran radioactivity log and perforated opposite Lansing lime as follows: 3759' to 3770' with 24 shots - bailed 5 gallons muddy water and stain of oil; 3735' to 3750' with 24 shots - bailed 5 gallons of muddy water; 3697' to 3708' with 24 shots - bailed 5 gallons of muddy water.

8-10-45 - Acidized zones 3759' to 3770', 3735' to 3750', and 3697' to 3708' with 1000 gallons through casing. Maximum pressure 550#; minimum pressure 400#. Swabbed 23 bbls. of oil per hour, no water for 6 hours off bottom.

8-12-45 - Perforated casing from 3670' to 3682' with 32 shots - swabbed 12 bbls. oil per hour for 5 hours off bottom.

8-16-45 - Perforated casing from 3718' to 3730' with 41 shots - swabbed 10 bbls. of oil and no water per hour for 4 hours.

8-19-45 - Acidized through casing from 3718' to 3730' with 2000 gallons; no pressure; time 31 minutes. After acidizing, swabbed 10 1/2 bbls. oil, no water per hour for 12 hours off bottom.

8-21-45 - Perforated casing opposite Lansing lime from 3640' to 3645' with 12 shots - swabbed 19 bbls. water and 1 bbl. oil per hour.

8-26-45 - Set plug at 3665' and squeezed off water zones from 3640' to 3645' with 200 sacks of cement under 3100# pressure.

8-30-45 - Drilled out cement to 3635'. Perforated casing opposite Lansing lime from 3619' to 3632' with 42 shots - swabbed 2 1/2 bbls. oil per hour for 5 hours.

8-31-45 - Perforated casing opposite Lansing lime as follows: from 3592' to 3606' with 39 shots - swabbed 7 bbls. oil for 2 hours; from 3582' to 3587' with 15 shots - swabbed 12 bbls. oil per hour for 2 hours; from 3548' to 3560' with 33 shots - swabbed 21 bbls. oil per hour for 11 hours.

9-9-45 - Drilled out cement to 3793' in order to produce well from 5 zones below packer as well has 4 zones above cement and packer. When plug was set at 3665' to squeeze off water zone from 3640' to 3645' the plug did not hole and cement went below the plug, plugging off producing sections below 3665'.

9-12-45 - Reperforated casing from 3759' to 3770' with 42 shots, 3735' to 3750' with 42 shots, and 3697' to 3708' with 42 shots; swabbed 20 bbls. oil per hour for 3 hours.

187

B. E. Boutz No. 2

9-13-45 - Reperforated casing from 3670' to 3682' with 24 shots, 3718' to 3730' with 21 shots; swabbed 20 bbls. oil per hour for 10 hours.

9-16-45 - Set packer at 3660' and swabbed 1 1/2 bbls. oil per hour for 4 hours. Pulled packer and run tubing and placed well on pump.

10-1-45 - Established a 24 hour physical potential of 561 bbls. oil. Daily allowable 25 bbl. oil.

Total Depth 3795'

Note: All depths are calculated from derrick floor, except formation log which is calculated from rotary table.

I, the undersigned, being duly sworn upon oath, state that this Well Record is true, correct and complete according to the records of this office, and to the best of my knowledge and belief.

*J. L. D.*  
District Superintendent


Subscribed and sworn to before me this 18th day of October, 1945.

*Ernie M. Gine*  
Notary Public

My commission expires October 21st, 1948.

FLD-BHD  
10-18-45  
LPC-3  
LEP-1  
File-1

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 11 1945



148