

15-179-05291-00 00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
500 INSURANCE BUILDING
212 NORTH MARKET
WICHITA 2, KANSAS

Form CP-1

RECEIVED
STATE CORPORATION COMMISSION

APR 6 1966

CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING APPLICATION FORM
File One Copy

Lease Owner Knigh t Casing Pulling Company
(Applicant)
Address Box 405, Chase, Kansas
Adell-Lan - KC Unit No. 702 or
Lease (Farm Name) B. H. Boutz No. " Well No. 2
C NESW NW
Well Location 990' N & 990' E of Sec. 2 Twp. 6S Rge. 27 (E) (W) W
w/4 Corner of
County Sheridan Field Name (If any)
Total Depth 3793' Oil Well Gas Well Input Well SWD Well D & A
Was well log filed with application? yes If not, explain:

Date and hour plugging is desired to begin Immediately

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of the person on the lease in charge of well owner Noel Knight
Address Chase, Kansas

Plugging Contractor Knigh t Casing Pulling Company License No. 436
Address Box 405, Chase, Kansas

Invoice covering assessment for plugging this well should be sent to Knigh t Casing Pulling Co.
Address Box 405, Chase, Kansas

and payment will be guaranteed by applicant.

Signed: M. J. Volin
Applicant or Acting Agent

Date: April 5, 1966

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

April 6, 1966

WELL PLUGGING AUTHORITY

Well No.	2
Lease	B. H. Bouts
Description	C NE SW NW 2-6-27W
County	Sheridan
Total Depth	3793'
Plugging Contractor	Co. Tools

Knight Casing Pulling Company
Box 405
Chase, Kansas

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Very truly yours,


J. P. Roberts, Administrator

Mr. W. L. Nichols Morland, Kansas
is hereby assigned to supervise the plugging of the above
named well.

15-179' 05291-00-00

WELL RECORD

OR Adell San KC Unit No 702
B. L. Boutz No. 2

RECEIVED
STATE CORPORATION COMMISSION
APR 6 1966

CONSERVATION DIVISION
Wichita, Kansas

Date Spudded: July 6, 1945
Drilling Completed: July 23, 1945
Date Tested: October 1, 1945

Loc: 990'N. and 990'W.
Corner of Sec. 2, T6S, R27E.
Sheridan County, Kansas

FROM	TO	FORMATION	FROM	TO	FORMATION
0	46	surface soil	1843	2063	Shale
46	75	Sand	2063	2250	Shale and shells
75	253	Shale and shells	2250	2892	broken line
253	732	Shale	2892	3795	Line
732	1843	Shale and shells			

Elevation 2546'

Perforations spaced 7-2-62 27/2 in

Ran 240' of 10 3/4"OD 27# 3 Ga. Amco spiral weld casing; set at 238'; cemented with 240 sacks of cement.

Top of Lansing Line 3547'

Ran 3822' 8" of 6"OD 18 7/8 RT #40 Electric weld casing; ran 6"OD RT packblu male and female float collar and 6"OD RT packblu guide shoe; set at 3792'; cemented with 300 sacks of cement.

Well was drilled to a total depth of 3795' in Lansing line.

8-8-45 - Drilled out cement to 3784'. Ran radioactivity log and perforated opposite Lansing line as follows: 3759' to 3770' with 24 shots - bailed 5 gallons muddy water and stain of oil; 3735' to 3750' with 24 shots - bailed 5 gallons of muddy water; 3697' to 3708' with 24 shots - bailed 5 gallons of muddy water.

8-10-45 - Acidized zones 3759' to 3770', 3735' to 3750', and 3697' to 3708' with 1000 gallons through casing. Maximum pressure 550#; minimum pressure 400#. Swabbed 23 bbls. of oil per hour, no water for 6 hours off bottom.

8-12-45 - Perforated casing from 3670' to 3682' with 32 shots - swabbed 12 bbls. oil per hour for 5 hours off bottom.

8-13-45 - Perforated casing from 3718' to 3730' with 41 shots - swabbed 10 bbls. of oil and no water per hour for 4 hours.

8-19-45 - Acidized through casing from 3718' to 3730' with 2000 gallons; no pressure; time 31 minutes. After acidizing, swabbed 10# bbls. oil, no water per hour for 12 hours off bottom.

8-21-45 - Perforated casing opposite Lansing line from 3640' to 3645' with 12 shots - swabbed 19 bbls. water and 1 bbl. oil per hour.

8-26-45 - set plug at 3665' and squeezed off water zones from 3640' to 3645' with 200 sacks of cement under 3100# pressure.

8-30-45 - Drilled out cement to 3635'. Perforated casing opposite Lansing line from 3619' to 3632' with 42 shots - swabbed 2 1/2 bbls. oil per hour for 5 hours.

8-31-45 - Perforated casing opposite Lansing line as follows: from 3592' to 3606' with 39 shots - swabbed 7 bbls. oil for 2 hours; from 3582' to 3587' with 15 shots - swabbed 12 bbls. oil per hour for 2 hours; from 3548' to 3560' with 33 shots - swabbed 21 bbls. oil per hour for 11 hours.

9-9-45 - Drilled out cement to 3795' in order to produce well from 5 zones below packer as well as 4 zones above cement and packer. When plug was set at 3665' to squeeze off water zone from 3640' to 3645' the plug did not hole and cement went below the plug, plugging off producing sections below 3665'.

9-12-45 - Reperforated casing from 3759' to 3770' with 42 shots, 3735' to 3750' with 42 shots, and 3697' to 3708' with 42 shots; swabbed 20 bbls. oil per hour for 8 hours.

B. H. BOUTZ NO. 2

.....

9-13-45 - Reperforated casing from 3670' to 3682' with 24 shots, 3718' to 3730' with 21 shots; swabbed 20 bbls. oil per hour for 10 hours.

9-16-45 - Set packer at 3630' and swabbed 1 1/2 bbls. oil per hour for 4 hours. Fulled packer and run tubing and placed well on pump.

10-1-45 - Established a 24 hour physical potential of 561 bbls. oil. Daily allowable 25 bbl. oil.

Total depth 3793'

Note: All depths are calculated from derrick floor, except formation logs which is calculated from rotary table.

.....

I, the undersigned, being duly sworn upon oath, state that this Well Record is true, correct and complete according to the records of this office, and to the best of my knowledge and belief.

[Signature]
District Superintendent

Subscribed and sworn to before me this 18th day of October, 1945.

[Signature]
Notary Public

My commission expires October 21st, 1945.

WLD-BED
10-18-45
LPC-3
LEF-1
file-1