

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-065-01092-00-00

RECEIVED
STATE CORPORATION COMMISSION

NOV 26 1963
11-26-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name John O. Farmer, Incorporated,

Complete Address: 370 West Wichita, Russell, Kansas.

Lease Name Peterson Well No. 1

Location CNE-SW Sec. 5 Twp. 6 Rge. (E) (W) 24

County Graham Total Depth 3805

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 5:30PM Day 21 Month 11 Year 1963

The Above well was plugged as follows:

204'--8 5/8" Surface pipe, cement circulated with 140 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx. cement

thru DP. Heavy mud to 190', set plug with 1/2 sack hulls and displaced 20

Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack hulls and 10

Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 11/27/63
INV. NO. 8176-W

Signed: W. L. Nichols
Well Plugging Supervisor