

15-179-05291-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 2 - 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Knight Casing Pulling Company,

Complete Address: Box #405, Chase, Kansas.

Lease Name B. H. Boutz Well No. 2

Location CNE-SW-NW Sec. 2 Twp. 6 Rge. (E) (W) 27

County Sheridan Total Depth 3793'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Above

Address: _____ License No. 436

Operation Completed: Hour 6:00PM Day 24 Month 4 Year 1966

The Above well was plugged as follows:

240'--10 3/4" Surface pipe, cement circulated with 240 Sx.

3792'--6" OD Production casing cemented with 300 Sx. Top perforations from 3670' to 3730'.

Pushed plug to 3650', sanded back to 3600' and set 5 Sx. cement with

dump bailer. Pulled 6" casing to 607' and circulated heavy gel mud, (Used

20 Sx. gel). Pulled 6" to 540' and displaced 20 Sx. cement thru 6". Pulled

6" to 210' and displaced 20 Sx. cement thru 6". Pulled 6", set rock bridge

@ 35' and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 5/2/66

INV. NO. 3132-W