

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-179-05621-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 9 1974  
12-9-74  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Continental Oil Company,

Complete Address 3535 NW 58th Street, Oklahoma City, Oklahoma.

Lease Name Adell L-KC Unit Well No. 403

Location NE-NE-SE Sec. 3 Twp. 6 Rge. (E) (W) 27

County Sheridan Total Depth 3824'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Pipe Pullers, Incorporated,

Address Box #486, Ellinwood, Kansas. License No. 462

Operation Completed: Hour 12:45 PM Day 2 Month 12 Year 1974

The above well was plugged as follows:

238'--10 3/4" Surface casing, cement circulated with 240 Sx.  
3823'--6" OD Production casing cemented on bottom with 300 Sx. Well plugged back to  
3793'. Top of perforations @ 3568'.

Pushed plug to 3550', sanded back to 3510' and set 5 Sx. cement with dump bailer.

Pulled 6" casing and squeezed well initially with 5 sacks hulls and 18 sacks gel  
following with 135 Cu. Ft. cement from 1275' to 950' then 21 sacks gel from 950' to  
260' and followed with 40 Cu. Ft. cement from 260' to 180' then 6 sacks gel from 180'  
to 30' and finally 15 Cu. Ft. cement from 30' to base of cellar. Maximum pump-in  
pressure-150#. FSIP-100#. Mudding and cementing by Sun Oil Well Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 12/10/74  
INV. NO. 433-W