

6010194

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-179-20760-0000

SE, SEC. 4, T 6 S, R 27 W

990 feet from #1S section line

990 feet from #1E section line

Lease Name Kingmuirhead Well # 1-4

County Sheridan

Well Total Depth 4340 141.05 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 330

TECHNICIAN'S PLUGGING REPORT

Operator License # 9123

Operator Name & Address Diamond Shamrock

Address Amarilo Texas

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilg. Co. License Number 6033

Address \_\_\_\_\_

Company to plug at: Hour: 11:30AM Day: 27 Month: 8 Year: 19 84

Plugging proposal received from Larry Benedict

(company name) Murfin Drilg. Co. (phone) \_\_\_\_\_

were: order 210 sx. cement 50/50 pozmix 6% gel 3% c.c.

1. sx. hulls 1. 8 5/8 plug 1. sx. flow seal

Heavy mud between all plugs.

Pump cement down drill pipe.

Elev. 2572 Anhydrite 2229-71 Arbuckle 4766

Dakota. 1475 Plugging Proposal Received by Nale F Balthazor

1097 = 1400

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 7:45PM Day: 27 Month: 8 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 4170 for 30 mi

25 sx. @ 4170

25 sx. @ 2250

100 sx. @ 1400 mixed with 1 sx flow seal.

40 sx. @ 340 Dumped 1 sx hulls, pushed plug to 40'

10 sx @ 40

Remarks: 10 sx in Rat Hole. Cementing to 500

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging STATE CORPORATION COMMISSION

DATE 9-10-84

SEP 04 1984

Signed Nale F Balthazor (TECHNICIAN)

INV. NO. 3605

CONSERVATION DIVISION  
Wichita, Kansas

9-4-84

FORM CP-2/3  
Rev. 01-84

SH  
Aug 31  
8