

DISTRICT CONSERVATION AGENT'S REPORT

15-179-00011-00-00

*Verbal*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NE NE SE

SEC. 1 TWP. 6 RGE. 27 W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Stuart

Operator Barnett Oil Co et al Address 417 First Race Bldg  
Wichita, Kans

Field \_\_\_\_\_ County Sheridan

Total Depth 4140 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 290' circulated with cement, 5 1/2" at 3851'

Cement and lane wells plugs 4140 to 3660 - top perforation

at 3648 - Chat 3660 to 3640 and 5 sax cement dumped at 3640,

Heavy mud to 299'- wood plug - rock and 15 sax cement, Heavy mud

to 25', wood plug and 10 sax cement.

~~2-22-49~~ 2-22-49

*[Signature]*  
District Conservation Agent

Date 2-17-49

**PLUGGING**  
FILE SEC 1 T 6 R 27 W  
BOOK PAGE 84 LINE 4

*[Handwritten mark]*