

DISTRICT CONSERVATION AGENT'S REPORT

15-179-05273-00-00

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 11-56

LOCATION SE SE NE

SEC. 5 TWP. 6 RGE. 27

Dry Hole Abandoned Oil Well X Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Carlton

Operator Derby Oil Co Address Wichita, Kans

Field County Sheridan

Total Depth 3820 Feet.

Plugging Contractor Bert Self

Plugging Contractor's License No. 48

Address

(Describe briefly the manner in which the well was plugged)

8 5/8" at 214' circulated with cement - 5 1/2" at 3819' with
100 sax cement behind.

800' cement in bottom hole - 2" tubing cut off at 2000' p
filled hole with sand to 2055' - set cement to 2011' - pulled
990' 5 1/2" - mudded hole to 210', set rock and 25 sax cement -
mud to 35', set rock and 10 sax cement to bottom cellar.

3819
400
3419
Edgar P. Lee
District Conservation Agent

Date 3-1-54

PLUGGING
FILE SEC 3 T 6 R 27w
BOOK PAGE 11 LINE 36

3-9-54