

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM

File One Copy

RECEIVED
STATE CORPORATION COMMISSION

JUN 09 1976

6-9-76
CONSERVATION DIVISION
Wichita, Kansas

API Number 15 - 179 - 20,242-00-00 (of this well)
Lease Owner A. L. Abercrombie, Inc.
Address 801 Union Center, Wichita, Kansas 67202
Lease (Farm Name) Glasgow "B" Well No. 1
Well Location App. C SW SW NW Sec. 21 Twp. 6 S Rge. ----- (E) -- 26 (W)
County Sheridan Total Depth 3959' Field Name Hortonville East
Oil Well X Gas Well Input Well SWD Well Rotary D & A
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin July 6, 1976 9:00 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

E. L. Abercrombie Address 32 Walnut, Hill City, Kansas 67642

Plugging Contractor Kelso Casing Pulling License No. unknown

Address Box 176, Chase, Kansas

Invoice covering assessment for plugging this well should be sent to:

Name A. L. Abercrombie, Inc.

Address 801 Union Center, Wichita, Kansas 67202

and payment will be guaranteed by applicant or acting agent.

Signed: 
Applicant or Acting Agent

Date: June 7, 1976

15-179-20242-00-00

CONTRACTOR'S WELL LOG

OWNER: Abercrombie Drilling, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 LEASE: GLASGOW "B" #1
 LOCATION: SW SW NW, Section 21-6S-26W,
 Sheridan County, Kansas
 SPUD DATE: January 21, 1970
 COMPLETION DATE: February 3, 1970
 GEOLOGIST: Jack K. Wharton

0	33	Clay and Sand
33	1274	Shale
1274	1355	Pyrite streaks and hard sand
1355	1465	Sand
1465	1580	Sand and Shale
1580	1765	Shale
1765	1825	Gyp and Sand
1825	1880	Shale
1880	2040	Sand
2040	2261	Shale
2261	2297	Anhydrite
2297	2660	Shale
2660	2878	Shale with lime streaks
2878	3690	Lime and shale
3690	3805	Lime
3805	3855	Lime and Shale
3855	3959	Lime
	3959	Rotary Total Depth

COPY

RECEIVED
 JUN 09 1976
 CONSERVATION DIVISION
 WISCONSIN

Drilled 336' of 9-5/8" surface hole and set 7-5/8", 20# casing, @ 331' w/185 sx. cement. Plug was down 9:15 P.M., 1-20-70. Cement circulated.
 Set 4 1/2" surface casing @ 3956'. Cemented w/35 sx. 50-50 posmix w/2% gel, 12# gilsonite per sx. and 65 sx. common cement w/2% gel, 10% salt, and friction reducer.

FORMATION SAMPLE TOPS	ELEVATION:	
Anhydrite	2261 (f 401)	2662' K.B.
B/Anhydrite	2297 (f 365)	2660' D.F.
Heebner	3717 (-1055)	2654' G.L.
Toronto	3741 (-1079)	
Lansing	3755 (-1093)	
Total Depth	3957	

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

Jerry A. Langrehr, President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the GLASGOW "B" #1, SW SW NW, Section 21-6S-26W, Sheridan County, Kansas, as of this 5th day of February, 1970.

ABERCROMBIE DRILLING, INC.

Jerry A. Langrehr
 Jerry A. Langrehr
 President

Sworn to before me, a Notary Public, in and for the County of Sedgwick, State of Kansas, as of the 5th day of February, 1970.

My Commission Expires:
 November 12, 1973

Sue J. McCoy
 Sue J. McCoy, Notary Public

State of Kansas



15-179-20242-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

June 10, 1976

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Glasgow "B"
Description	App. C SW SW NW Sec. 21-6-
County	Sheridan 26W
Total Depth	3959
Plugging Contractor	Keiso Casing Pulling


A. L. Abercrombie Drilling, Inc.
801 Union Center
Wichita, KS 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, P. O. Box 9, Rt. #1, Falco, KS 67657
is hereby assigned to supervise the plugging of the above named well.