

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21043-00-01
Spot: SESWSE Sec/Twnshp/Rge: 17-26S-8E
330 feet from S Section Line, 1650 feet from E Section Line
Lease Name: DUNNE B Well #: 2
County: BUTLER Total Vertical Depth: 2791 feet

Operator License No.: 6804
Op Name: LACHENMAYR, HOWARD DBA LACHE
Address: 904 EMMALINE
NEWTON, KS 67114

PROD Size: 4.5 feet: 2791 75 SX CMT
SURF Size: 7 feet: 162 50 SX CMT

\$90⁷¹

Well Type: EOR UIC Docket No: E19808.2 Date/Time to Plug: 03/31/2005 12:00 PM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. D/B/A BRADEN PETROLEUM & WELL PLUGGING
Proposal Rcvd. from: HOWARD LACHENMAYR Company: LACHENMAYR OIL COMPANY Phone: (316) 284-7150

Proposed Plugging Method: See actual report

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/31/2005 5:00 PM KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Sanded back 50' above perforations with 4 sacks of cement on top of sand. Casing had been cemented in from 500' to surface. Shot casing at 450'; could not pump in. Filled 4-1/2" casing from 300' to surface with 32 sacks of 60/40 posmix with 4% gel.

Braden Petroleum and Well Plugging

60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
2716	2732		
RECEIVED KCC DISTRICT #2 APR 11 2005 WICHITA, KS			
RECEIVED APR 28 2005 KCC WICHITA			

Remarks:

Plugged through: TBG

District: 02

Signed 

(TECHNICIAN)

INVOICED
DATE 4.28.05
INV. NO. 2005061480