

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21274-00-00
Spot: SEWNNE Sec/Twnshp/Rge: 5-21S-6W
4290 feet from S Section Line, 1650 feet from E Section Line
Lease Name: RENOLLET Well #: 1
County: RICE Total Vertical Depth: 3534 feet

Operator License No.: 8917
Op Name: GUSTUS, DEAN DBA JD PRODUCTION
Address: 701 MAIN
GENESEO, KS 67444

PROD Size: 4.5 feet: 3534 250 SX CMT
SURF Size: 8.625 feet: 164 135 SX CMT

11486

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 737-3410

Proposed Plugging Method: Sand perms to 3390' and put 4 sxs cement on top; cut off casing; pull to 1000' and pump 35 sxs cement; pull casing to 600' and pump 35 sxs cement; pull casing to 250' and circ cement to surf.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 03/29/2005 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 3390' and put 4 sacks of cement on top. Cut casing off at 2450'. Pulled casing to 1000' and pumped 35 sacks of cement. Pulled casing to 600' and pumped 35 sacks of cement. Pulled casing to 250' and circulated cement to surface.

Copeland Cement #24956
60/40 posmix with 4% gel

Perfs:

Top	Bot	Thru	Comments
3442	3457		

RECEIVED
KCC DISTRICT #2
APR 14 2005
WICHITA, KS
RECEIVED
MAY - 5 2005
KCC WICHITA

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 5-5-05
INV. NO. 2005061521