

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20791-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 27-10S-18W
3630 feet from S Section Line, 2310 feet from E Section Line
Lease Name: EILERS EAST Well #: 2
County: ROOKS Total Vertical Depth: 3635 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

PROD Size: 4.5 feet: 1412 400 SX CMT
SURF Size: 8.625 feet: 211 150 SX CMT

118¹⁴

Well Type: SWD UIC Docket No: D19698.0 Date/Time to Plug: 05/02/2005 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: THAD STARR Company: AMERICAN ENERGIES CORPORAT Phone: (316) 263-5785

Proposed Plugging Method: Ordered 150 sxs 60/40 pozmix - 10% gel - 500# hulls.
Express Well Service pulled into 4 1/2" 40,000 over - could not get loose.
4 1/2" appeared to be cemented in.
LK Wireline could not get gun down 4 1/2" tubing to perforate.
Could only get to 28'. Took pump in rate of 3 1/2 BBL per minute.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 05/02/2005 11:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Allied rigged to 4 1/2" tubing with a swedge and pumped 30 sxs 60/40 pozmix neat followed with 40 sxs cement with 200# hulls mixed in.
Took off swedge. LK Wireline attempted to perforate - gun would only go down 4 1/2" - 28'.
Tied back onto 4 1/2" with a swedge and pumped 80 sxs cement with 150# hulls mixed in.
Max. P.S.I. 600#. S.I.P. 250#.
Tried to cut hole in 8 5/8" to weld on nipple.
Backside was full of cement.

Perfs:

Top	Bot	Thru	Comments
1030	1105		

RECEIVED
MAY - 5 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #18702.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

INVOICED

DATE 5-5-05
INV. NO. 2005061517

MAY 03 2005

