

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-189-⁰⁰⁰²⁴00487-0000

LEASE NAME MCCREERY

WELL NUMBER 2-10

660' FSL Ft. from S Section Line

1976' FWL Ft. from E Section Line

SEC. 10 TWP. 31S RGE. 37W (E) or (W)

COUNTY STEVENS

Date Well Completed 06/21/60

Plugging Commenced 04/26/05

Plugging Completed 04/27/05

TYPE OR PRINT
NOTICE: Fill out completely
and return to GORS. Div.
office within 30 days

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # (727) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/10/04, 03/07/05 (date)

by DAVID WILLIAMS (KCC District Agent's Name)

is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation COUNCIL GROVE Depth to Top 2990 3071 GL Bottom 3071 6139 T.D. 6139 2990

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
COUNCIL GROVE	GAS	2847'	2918'	13 3/8"	578'	0
				8 5/8"	3061'	924'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

4/26-27/05 P&A Op witnessed by S. Durant, KCC. POOH tbq. rods, subs. CIBP 2800', load hole w/ 71 bbl 9 ppg 36 cp mud & 50 sx cmt 1650'-1500' & 85 bbl mud. Cut 8 5/8" csg @ 924'. Circ w/ 70 bbl mud & 75 sx cmt plug 600'-500' & disp w/30 bbl mud. Load hole to 40' w/9 ppg mud. Pmp 25 sx cmt plug from 40'-0'. Cut 13 3/8" csg 3' bgl, weld trash cover ID plate. RDMO.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.


LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039

SUBSCRIBED AND SWORN TO before me this 29th day of April, 20 05

My Commission Expires: 3/23/06 Notary Public



USE ONLY ONE SIDE OF EACH FORM

Form CP-4
Revised 05-88