

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 South Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-137-00,511-00-00

LEASE NAME FOUGHT

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 60 days.

WELL NUMBER #7 (NW SW SE)

990 Ft. from S Section Line  
2310 Ft. from E Section Line

LEASE OPERATOR John O. Farmer, Inc.

SEC. 25 TWP. 3S RGE. 24 XXXXXX (W)

ADDRESS P.O. Box 352, Russell, KS 67665

COUNTY Norton

PHONE# (785) 483-3144 OPERATORS LICENSE NO. 5135

Date Well Completed Oct., 1957

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Commenced 10:15 A.M., 4-7-05

Plugging Completed 11:00 A.M., 4-7-05

The plugging proposal was approved on \_\_\_\_\_ (date)  
by \_\_\_\_\_ (District #4) \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Lansing "J", "K", "L" & Marmaton Depth to Top 3654' Bottom 3734' T.D. 3778'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Lansing & Marmaton	oil & water	3654'	3734' OA	10-3/4"	265'	-0-
				5-1/2"	3775'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Hooked on to 5-1/2" casing; mixed 325 sks. 60/40 Pozmix, 10% gel w/700# hulls - maximum pressure 700 PSIG; shut in @ 500 PSIG. Hooked on backside & mixed 50 sks. cement - no pressure - not on vacuum - shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company, Inc. License No. \_\_\_\_\_

Address P.O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.

STATE OF Kansas COUNTY OF Russell, ss.

John O. Farmer III, President of John O. Farmer, Inc. XXXXXXXXXXXXXXXXXXXXXXXX (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John O. Farmer III

(Address) P.O. Box 352, Russell, KS 67665


SUBSCRIBED AND SWORN TO before me this 27th day of April 20 05

Margaret A. Schulte  
Notary Public

Margaret A. Schulte

Form CP-4

Revised 05-88



*[Handwritten mark]*



W E L L L O G

OPERATOR: WOOD RIVER OIL & REFINING CO  
Koch Building  
Wichita, Kansas

FARM NAME: #7 FOGHT

CONTR: K & E DRILLING, INC.  
719 Union Center Building  
Wichita, Kansas

LOCATION: 660' West of Owners East  
line of Wells & 660'  
North of the South line  
of wells in SW/4 of  
Section 25-36-24W  
Norton County, Kansas

CASING: 10-3/4" @ 265' (160 sx)  
5-1/2" @ 3775 (75 sx)

PRODUCTION: unknown

T.D. 3778'

ELEVATION: unknown

COPY

FORMATION RECORD

Depths shown indicate bottom of formation encountered.

Shale	80
Sand	95
Shale	165
Sand & Shale	200
Shale	265
Shale	1175
Sand & Shale	1635
Shale	2045
Anhydrite	2075
Shale	2290
Shale & Shells	2480
Shale & Lime	2655
Shale & Lime	3010
Lime & Shale	3110
Shale & Lime	3270
Lime & Shale	3400
Lime	3750
Lime & Sable	3778
R.T.D.	3778

CERTIFICATION

STATE OF KANSAS }  
COUNTY OF SEDGWICK } SS:

I, Dale Silcott of the K & E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the log of the #7 FOGHT well.

*Dale Silcott*  
Dale Silcott

Subscribed and sworn to before me on this the 24th day of September,

1957.

*Patricia M. Edwards*  
Patricia M. Edwards, Notary Public

My commission expires: 11 August 1958.

RECEIVED  
APR 29 2005  
KCC WICHITA