

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 South Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-137-00,510 ~~00~~ ~~00~~

LEASE NAME FOUGHT

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 60 days.

WELL NUMBER #6 (SW SE SW)

330 Ft. from S Section Line
1650 Ft. from W Section Line

LEASE OPERATOR John O. Farmer, Inc.

SEC. 25 TWP. 3S RGE. 24 XXXXXX (W)

ADDRESS P.O. Box 352, Russell, KS 67665

COUNTY Norton

PHONE# (785) 483-3144 OPERATORS LICENSE NO. 5135

Date Well Completed May, 1954

Plugging Commenced 11:30 A.M., 4-7-05

Plugging Completed 2:45 P.M., 4-7-05

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)
by _____ (District #4) _____ (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation Toronto, Lansing "H", "J", "K", & "L" Depth to Top 3458' Bottom 3646' T.D. 3737'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Toronto & Lansing	oil & water	3458'	3646' OA	8-5/8"	261'	-0-
				5-1/2"	3737'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Mixed 50 sks. cement w/300# hulls; 18 sks. gel, 200 sks. cement w/200# hulls - down 5-1/2" casing; maximum pressure 400 PSIG. Hooked on backside & mixed 25 sks. cement w/100# hulls - 100 PSIG maximum pressure; shut in @ 50 PSIG.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company, Inc. License No. _____

Address P.O. Box 31, Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: John O. Farmer, Inc.

STATE OF Kansas COUNTY OF Russell, ss.

John O. Farmer III, President of John O. Farmer, Inc. XXXXXXXXXXXXXXXXXXXXXXXX (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John O. Farmer III

(Address) P.O. Box 352, Russell, KS 67665


SUBSCRIBED AND SWORN TO before me this 27th day of April, 20 05

Margaret A. Schulte
Notary Public

Margaret A. Schulte

Form CP-4

Revised 05-88



Se

ALLIED CEMENTING CO., INC. 19260

Federal Tax I.D.# ~~XXXXXXXXXX~~

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
OAKLEY

DATE <u>4-7-05</u>	SEC <u>25</u>	TWP. <u>35</u>	RANGE <u>24W</u>	CALLED OUT	ON LOCATION <u>11:15 AM</u>	JOB START <u>11:30 AM</u>	JOB FINISH <u>2:45 PM</u>
FOUGHT LEASE	WELL # <u>6</u>	LOCATION <u>NORTON 6S-4W-1N-1W-N 2N</u>			COUNTY <u>NORTON</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR NONE OWNER SAME

TYPE OF JOB OLD HOLE

HOLE SIZE _____ T.D. _____ CEMENT AMOUNT ORDERED 275 SKS 60/40 10210866L

CASING SIZE 5 1/2" DEPTH _____ 1866L 600# HULLS

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____ COMMON 165 SKS @ 9.55 1575.75

MEAS. LINE _____ SHOE JOINT _____ POZMIX 110 SKS @ 4.50 495.00

CEMENT LEFT IN CSG. _____ GEL 42 SKS @ 13.00 546.00

PERFS. _____ CHLORIDE _____ @ _____

DISPLACEMENT _____ ASC _____ @ _____

EQUIPMENT

PUMP TRUCK CEMENTER TERRY HULLS 600# @ 20.00 1200.00

191 HELPER WAYNE @ _____

BULK TRUCK _____ @ _____

218 DRIVER MIKE LARRY @ _____

BULK TRUCK _____ @ _____

_____ DRIVER _____ @ _____

HANDLING 323 SKS @ 1.50 484.50
MILEAGE 5 1/4 PER SK / MILE 1510.45
TOTAL 4731.90

REMARKS:

MIX 50 SKS CEMENT WITH 300# HULLS
18 SKS GEL 200 SKS CEMENT WITH
200# HULLS DOWN 5 1/2 CASING MAX
PRESSURE 400 PSI SHUT IN 100 PSI
HOOK ON BACKSIDE MIX 25 SKS
CEMENT WITH 100# HULLS 100 PSI MAX
SHUT IN 50 PSI

2nd well SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE _____ 280.00

EXTRA FOOTAGE @ _____

MILEAGE 85 ME @ N/C

MANIFOLD @ _____

_____ @ _____

TOTAL 280.00

CHARGE TO: John O. Farmer

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL _____

TAX _____

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Deane C. [Signature]

PRINTED NAME _____

RECEIVED
APR 29 2005
KCC WICHITA

WR1091

bc

COMPANY: WOOD RIVER OIL & REFINING CO., INC.
 CONTRACTOR: EMPIRE DRILLING COMPANY
 FARM: CORA FOUGHT #6
 LOCATION: SW SE SW, SEC. 25-3-24
 NORTON COUNTY, KANSAS
 COMMENCED: 5-11-54
 COMPLETED: 5-21-54

COPY

0	TO	281	SURFACE HOLE
281	TO	1993	SHALE AND SHELLS
1993	TO	2022	ANHYDRITE
2022	TO	2795	SHALE AND SHELLS
2795	TO	3045	SHALE AND LIME
3045	TO	3215	LIME AND SHALE
3215	TO	3320	SHALE AND SHELLS
3320	TO	3460	LIME AND SHALE
3460	TO	3635	LIME
3635	TO	3737	LIME AND SHALE
3737			R.T.D.

SET 261' OF 8-5/8" SURFACE CASING, CEMENTED WITH 135 SACKS OF CEMENT.

ELEVATION: 2407 D. F.

C E R T I F I C A T I O N

I, DAN J. KORNFELD, DO HEREBY CERTIFY THAT THE ABOVE AND FOREGOING IS A TRUE AND CORRECT COPY OF THE LOG ON THE CORA FOUGHT #6, SW SE SW, SECTION 25, TOWNSHIP 3, RANGE 24 WEST, NORTON COUNTY, KANSAS AS REFLECTED BY THE FILES OF THE EMPIRE DRILLING COMPANY.

Dan J. Kornfeld
 DAN J. KORNFELD

SUBSCRIBED AND SWORN TO BEFORE ME A NOTARY PUBLIC WITHIN AND FOR SEDGWICK COUNTY, KANSAS THIS 25 DAY OF MAY 1954.

MY COMMISSION EXPIRES MAY 5, 1956

Mary Timmeis
 NOTARY PUBLIC

RECEIVED
 APR 29 2005
 KCC WICHITA