

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-00803-00-00
Spot: SWSW Sec/Twnshp/Rge: 35-9S-25W
660 feet from S Section Line, 4620 feet from E Section Line
Lease Name: VERONICA Well #: 1
County: GRAHAM Total Vertical Depth: 4021 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

PROD Size: 4.5 feet: 4016 130 SX CMT
SURF Size: 8.625 feet: 235 125 SX CMT

#130⁶⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/25/2005 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: DENNIS KIRMER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed DV Tool at 2049' with unknown cement.
Plugging 1972 - Squeezed at 3845'-3863' w/250 sxs.
Method: 1972 - Squeezed at 1516'-1830'-2127' w/200 sxs-squeezed again at 1453'-2127' w/600 sxs.
1985 - Squeezed at 1425'-2200' w/260 sxs.
1988 - Squeezed at 1710'-1732' w/20 sxs and 3225'-3256' w/15 sxs.
1991 - Squeezed at 3340'-3370' w/250 sxs.
1994 - Squeezed at 3350'-3382' w/15 sxs and 2917'-2979' w/185 sxs.
Total of 1795 sxs in squeezes.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/25/2005 1:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Ran tubing to 3725' w/50 sxs ceent and 200# hulls.
Pulled tubing to 2710' - spotted 50 sxs cement and 200# hulls.
Pulled tubing to 1700' - spotted 50 sxs cement and 100# hulls.
Pulled tubing to 675' and circulated with 20 sxs cement and 100# hulls.
Pulled all tubing and squeezed with 20 sxs cement.
Max. P.S.I. 500#. Shut in.
Tied to annulus and squeezed 110 sxs cement.
Max. P.S.I. 350#. Shut in.
Total of 300 sxs 60/40 pozmix - 10% gel and 600# hulls.
Dakota 1028' - 1328'. Anhydrite 2170' - 2210'.

Perfs:

Top	Bot	Thru	Comments
4001	4004		
3995	3998		
3976	3981		
3955	3961		
3859	3863		

RECEIVED
MAY - 4 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY, KELLER TANK-WATER.

Plugged through: TBG

District: 04

Signed *Roger A. Moses*
(TECHNICIAN)

INVOICED
5.4.05
2005061511

MAY 02 2005

THE KIMBARK COMPANY #1 VERONICA 35-9-25W
C SW SW

Contr. KIMBARD EXPLORATION GRAHAM County

E 2533RB Comm. 4-27-59 Comp. 6-26-59 IP 159 BOPD

Tops	Depth	Datum
Aw	2170	+363
HEEB	3775	-1242
TOR	3798	-1265
LANS	3816	-1283
TD	4021	-1488

Casing
8" 235
4" 4016
DST 3785-3806/1 HR, 40' M, BHP 240/
DST 3806-25/45", 30' M, SPKS O, BHP 1155/
DST 3834-3852/1 HR, 840' W, SSG & O, BHP 1195/
DST 3852-65/1 HR, 240' G, 65' V H OCM, BHP 1250/
DST 3936-60/30", 20' M, BHP 0/
DST 3966-83/1 HR, 320' G, 40' O & OCM, 520/
CO 4020: ACID 500: 1 BOPH, NW: PB 4000:
PERF 3975-80: ACID 250: 7 BOPH: PB 3960:
PERF 3860-64: ACID 500: WTR: SQZ: PERF 3860-64
CO 4020

EMOR POOL

+	+	+
+	+	+
+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS