

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-02507-00-00
Spot: N2SESW Sec/Twnshp/Rge: 22-12S-18W
990 feet from S Section Line, 3300 feet from E Section Line
Lease Name: BEMIS-SHUTTS (REEDER) Well #: 1-5
County: ELLIS Total Vertical Depth: 3669 feet

Operator License No.: 4952
Op Name: SCHLOBOHM, STARR F.
Address: 47 MICHAWANIC ROAD #3D
SANBORNVILLE, NH 03872

PROD Size: 5.5 feet: 3668 w/100 sxs cmt
SURF Size: 8.625 feet: 200

#119²⁴

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/29/2005 11:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOHN DRISCOLL Company: SCHLOBOHM, STARR F. Phone: (603) 522-9760

Proposed Plugging Method: Emergency plug with rig over hole.
Brought 400 sxs 60/40 pozmix - 10% gel - 1000# hulls.
Tubing and packer in hole at 2500'.
Perf and squeezed at 1384' - 1385' - 6 holes with 295 sxs.
Fluid level 628'. Possible casing leak at 850'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/29/2005 1:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 2400' - pumped 150 sxs cement with 700# hulls - mixed in to circulate cement to surface.
Pulled tubing and tied onto 5 1/2" casing - pumped 150 sxs 60/40 pozmix with 300# hulls mixed in.
Max. P.S.I. 500#. S.I.P.100#.
8 5/8" was full of cement. Visual check.

Perfs:

RECEIVED
MAY - 4 2005
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS REEDER #5. ALLIED CEMENTING COMPANY-TICKET #161156.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

INVOICED

DATE 5-2-05
INV. NO 2005061512

Form CP-2/3

MAY 02 2005

PETROLEUM, INC

#5 REEDER

22-12-18W
N2 SE SW

Contr. GARVEY DRILLING CO

ELLIS

County

E 2156 RB

Comm.

Comp.

2-13-53

IP

100 BOPD

Tops	Depth	Datum
Ank	1405	7751
HEEB	3352	-1196
LANS	3395	-1239
ARB	3656	-1500
TD	3669	-1513

Casing

8" 200

5" 3668

DST 3425-50/1 HR, 570' OIL
DST 3469-80/, 40' MUD, 60'
SL O & GCM, 60' O & GCM
DST 3496-3519/1 HR, 1980'
GAS, 1310' OIL, 130' WTR
BHP 1125#
DST 3655-81/1 HR, 15' MUD,
BHP 0#
DST 3662-69/1 HR, 60' FREE
OIL, 90' H OCM, BHP 930#
DP, 4 BOPH, NO WTR, ACID
500

KOBLITZ

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

W. G. W. 22-12-18W