

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-01616-00-00
Spot: NWNENW Sec/Twnshp/Rge: 10-9S-19W
4950 feet from S Section Line, 3630 feet from E Section Line
Lease Name: ROSITCAL C Well #: 2
County: ROOKS Total Vertical Depth: 3429 feet

Operator License No.: 5552
Op Name: GORE OIL COMPANY
Address: 202 SOUTH ST. FRANCIS PO BOX 2757
WICHITA, KS 67201

PROD Size: 5.5 feet: 3429 150 SX CMT
SURF Size: 8.625 feet: 346 155 SX CMT

11144

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2005 3:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Ordered out 300 sxs Swift Multi-Density Cement and 800# hulls.
Cleaned out to 3370' C.I.B.P. - drilling mud and sand.
Pulled TOH - ran bit - couldn't get below 950' - bad casing - decided to plug well.
Fluid level 150' from surface. CIBP at 3370'.
LKC perfs 3184' - 3370'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/26/2005 12:20 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 950'.
Swift Services pumped 85 sxs Swift Multi-Density neat - circulated cement.
PTOH. Squeezed down 5 1/2" casing with 175 sxs SMD with 800# hulls.
Max. P.S.I. 400#. Shut in one hour.
Pumped 40 sxs SMD with 50# S.I.P.
04-26-2005 - Swift Services pumped 40 sxs SMD cement with 100# hulls down backside.
Max. P.S.I. 150#. S.I.P. 50#.
Topped off 5 1/2" casing with 15 sxs.

Perfs:

Top	Bot	Thru	Comments
3428	3431		
3179	3427		

RECEIVED
MAY - 2 2005
KCC WICHITA

Remarks: SWIFT SERVICES, INC.

Plugged through: TBG

District: 04

AD

Signed Richard Williams
(TECHNICIAN)

INVOICED

DATE 5-2-05
CPL NO. 2005061501

APR 28 2005

SOHIO, ET AL #2 ROSTICAL 'B' 10-9-19W.
 NW NE NW

Contr. STRAIN DRLG _____ ROOKS County

E 2019 Comm. _____ Comp. 8-11-50 IP 3000 BOPD/DRAWDOWN

Tops	Depth	Datum	Casing
Awk	1417	+602	8" 346
HEEB	3139		5" 3428
LANS	3178		23 BOPH: A/1000
ARB	3428		
TD	3431		

NOVOTNY POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

IMAGED