

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-23122-00-00  
Spot: SENWSESW Sec/Twnshp/Rge: 15-15S-18W  
970 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: WETTA Well #: 2  
County: ELLIS Total Vertical Depth: 3757 feet

Operator License No.: 8902  
Op Name: MAYS, SAM W., JR.  
Address: PHILTOWER BUILDING 427 S BOSTO  
TULSA, OK 74103

PROD Size: 4.5 feet: 3616 150 SX CMT COMMON  
SURF Size: 8.625 feet: 558 w/300 sxs cmt

#122<sup>10</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/22/2005 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: SAM MAYS Company: MAYS, SAM W., JR. Phone: (918) 382-9170

Proposed Plugging Method: Ordered out 215 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Well squeezed with cement to surface.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/22/2005 10:00 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Annulus full of cement.  
Swaged onto 4 1/2" - mixed and pumped 215 sxs cement with 500# hulls.  
Max. P.S.I. 1200#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3609	3613		
3562	3566		
3552	3556		
3496	3500		
3466	3470		
3358	3363		


RECEIVED  
MAY - 2 2005  
KCC WICHITA

Remarks: LEASE ALSO KNOWN AS WETTA #2-15. ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

  
(TECHNICIAN)


INVOICED

DATE 5.2.05  
INV. NO. 2005061504

Form CP-2/3

APR 27 2005

GRANT OIL, INC. 15-15-18W  
 9150 W. JEWELL, #106 #2-15 WETTA 970' FSL &  
 LAKEWOOD, CO 80226 940' FEL, SW/4  
 CONTR ALLEN DRILLING CTY ELLIS  
 GEOL FIELD LEIKER  
 ELV 2052 KB SPD 10/25/82 CARD ISSUED 12/30/82 IP P 25 BOPD, NW  
 2047 81  
 API 15-051-23,122 CONG SD 3609.5-3613.5



LOG	Tops	Depth Datum
HEEB	.....	3288-1236
LANS	.....	3336-1284
BKC	.....	3568-1516
CONG LM	.....	3578-1526
CONG SD	.....	3509-1557
ARB	.....	3541-1589
RTD	.....	3716-1664

8 5/8 " 558/300SX; 4 1/2 " 3715/150SX  
 DST (1) 3602-16 (CONG) / 30-60-45-90, REC 75' MO (50% O,  
 40% M, 10% W), SIP 363-352#, FP 34-34 / 34-34#, HP 2050-  
 2037#  
 DST (2) 3626-44 (CONG, ARB) / TIMES NA, REC 20' MW, SIP  
 1122-1122#, FP 34-34 ' 45-45#, HP 2048-2037#  
 MICT - CO, PF (CONG SD) 3609.5-13.5 W/4 SPF, AC 250G, SWB  
 DWN, GSO, SET 2 3/8 " TBG AT 3609', POP, P 25 BOPD, NW,  
 12/6 82

NOTE: ORIGINALLY FIRST REPORTED IN SW SW NE; 1ST COR-  
 RECTION CHANGED LOC TO NE SW SW

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS