

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-197-20265-00-00
Spot: W2E2NE Sec/Twnshp/Rge: 33-13S-13E
1320 feet from N Section Line, 990 feet from E Section Line
Lease Name: THOMPSON Well #: 1-33
County: WABAUNSEE Total Vertical Depth: 3065 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

CIBP Size: feet: 1890 2 SX CMT
PROD Size: 7 feet: 3057 265 SX CMT
SURF Size: 9.625 feet: 364 190 SX CMT

99⁶¹

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/05/2004 8:00 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Revd. from: MICHEAL POND Company: _____ Phone: (620) 482-1006

Proposed Plugging Method: SET CIBP @ 1890'. DUMP 2 SX CMT ON CIBP. CUT OFF 7" CASING @ 1200'. SPOT 20 SX CMT FROM 1150'-1200'. PUMP 170 SX CLASS H CMT FROM SURFACE DOWN. CUT OFF AND CAP 9-5/8" CASING @ 4'. SPACE PLUGS WITH HEAVY MUDS.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 08/14/2004 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

set cibp @ 1870' dump 2 sxs. Cement on top of cibp., cut off casing @ 810', pump 20 sxs. Cement, pump 120 sxs. Cement to surface, heavy mud between plugs. Cut surface casing off 4' below gl.

Perfs:

Top	Bot	Thru	Comments
2230	2232		
2141	2143		
2016	2017		
1904	1905		

RECEIVED
KCC DISTRICT #3

APR 25 2005 MH

CHANUTE, KS

RECEIVED
MAY - 2 2005
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern
(TECHNICIAN)

INVOICED

DATE 5-2-05
SER. NO. 2005061493