

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-111-20424-00-00
Spot: NE Sec/Twnshp/Rge: 27-15S-11E
1320 feet from N Section Line, 1320 feet from E Section Line
Lease Name: COFFMAN Well #: 1-27
County: LYON Total Vertical Depth: 3271 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

CIBP Size: feet: 2800
PROD Size: 7 feet: 3103 310 SX CMT
SURF Size: 9.625 feet: 253 110 SX CMT

106 31

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/05/2004 8:00 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: MICHEAL POND Company: _____ Phone: (620) 482-1006

Proposed Plugging Method: BULL HEAD 2 SX HULLS AND 30 SX CLASS H CMT TO COVER PERFS. CUT OFF 7" CASING AT 12000'. SPOT 20 SX CMT FROM 1150-1200'. PUMP 125 SX CMT FROM SURFACE DOWN. CUT OFF AND CAP 9-5/8" 4' BELOW GL. SPACE PLUGS WITH HEAVY MUD.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 08/09/2004 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

SET CIBP @ 2240' DUMP 2 SXS. CEMENT ON TOP OF CIBP. CUT OFF CASING @ 641' PUMPED 20 SXS. CEMENT, 125 SXS. CEMENT FROM 300' TO SURFACE. HEAVY MUD BETWEEN PLUGS.

Perfs:

Top	Bot	Thru	Comments
2327	2330		
2302	2306		
2274	2275		

RECEIVED
KCC DISTRICT #3
APR 25 2005
CHANUTE, KS MH

RECEIVED
MAY - 2 2005
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern
(TECHNICIAN)

INVOICED
DATE 5-2-05
INV. NO. 2005061493