

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-111-20425-00-00
Spot: E2W2E2NE Sec/Twnshp/Rge: 7-16S-12E
1320 feet from N Section Line, 985 feet from E Section Line
Lease Name: HIEFNER Well #: 1-7
County: LYON Total Vertical Depth: 3018 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

CIBP Size: feet: 1510 2 SX CMT
CIBP Size: feet: 2040
CIBP Size: feet: 2290
PROD Size: 7 feet: 3012 320 SX CMT
SURF Size: 9.625 feet: 244 130 SX CMT

A 98⁰⁹

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/05/2004 8:00 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: MICHEAL POND Company: _____ Phone: (620) 482-1006

Proposed Plugging Method: SET CIBP @ 1510, DUMP 2 SX CMT ON CIBP. CUT OFF 7" CASING @ 1300'. SPOT 20 SX (50') CMT ON TOP OF 7" CASING. SPOT 125 SX CLASS H CMT TO SURFACE. HEAVY MUD BETWEEN PLUGS. CUT AND CAP 9-5/8" CASING 4' BELOW GL.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 08/11/2004 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

SET CIBP. @1510', DUMP 2 SXS CEMENT ON TOP OF CIBP. CUT OFF CASING @ 641', PUMPED 20 SXS CEMENT, CIRC. CEMENT FROM 320' TO SURFACE. HEAVY MUD BETWEEN PLUGS.

Perfs:

Top	Bot	Thru	Comments
1898	1901		
1787	1790		
1775	1778		
1683	1687		
1634	1637		
1427	1429		
1413	1415		

RECEIVED
KCC DISTRICT #3

APR 25 2005

CHANUTE, KS

MH

RECEIVED
MAY - 2 2005
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern
(TECHNICIAN)

INVOICED
DATE 5-2-05
INV. NO. 2005061493