

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-111-20426-00-00
Spot: NE Sec/Twnshp/Rge: 14-16S-12E
1320 feet from N Section Line, 1320 feet from E Section Line
Lease Name: AHLSTROM TRUST Well #: 1-14
County: LYON Total Vertical Depth: 3082 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

CIBP Size: feet: 2870 2 SX CMT
PROD Size: 7 feet: 2886 290 SX CMT
SURF Size: 9.625 feet: 244 120 SX CMT

\$100¹⁷

Well Type: SWD UIC Docket No: _____ Date/Time to Plug: 08/05/2004 8:00 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: MICHEAL POND Company: _____ Phone: (620) 482-1006

Proposed Plugging Method: SET CIBP @ 2870'. DUMP 2 SX CMT ON CIBP. CUT OFF 7" CASING @ 1200'. SPOT 20 SX CMT FROM 1150'-1200'. PUMP 125 SX CLASS H CMT FROM SURFACE DOWN. SPACE CMT PLUGS WITH HEAVY CMT. CUT OFF AND CAP 9-5/8" 4' BELOW GL.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 08/10/2004 5:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

SET CIBP @ 2870' DUMP 2 SXS CEMENT ON CIBP. CUT OFF 7" CASING @ 1200' SPOT 20 SXS CEMENT FROM 1150' TO 1200'. PUMP 125 SXS. CEMENT FROM SURFACE DOWN, HEAVY MUD BETWEEN PLUGS. CUT & CAP CASING 4' BELOW G.L.

Perfs:

Top	Bot	Thru	Comments
2886	3082		

RECEIVED
MAY - 2 2005
KCC WICHITA

RECEIVED
KCC DISTRICT #3
APR 25 2005
M H
CHANUTE, KS

Remarks:

Plugged through: TBG

District: 03

Signed Michael Heffern
(TECHNICIAN)

INVOICED
DATE 5-2-05
INV. NO. 2005061493