

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-29120-00-00
Spot: SWNENWSW Sec/Twnshp/Rge: 23-26S-18E
2000 feet from S Section Line, 4330 feet from E Section Line
Lease Name: CANNON A Well #: 36
County: ALLEN Total Vertical Depth: 865 feet

Operator License No.: 5488
Op Name: TWM PRODUCTION CO.
Address: 1150 HWY 39
CHANUTE, KS 66720

SURF Size: 7 feet: 20

35⁰⁰

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/25/2005 1:00 PM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY
Proposal Rcvd. from: MIKE WIMSETT Company: W & W PRODUCTION COMPANY Phone: (620) 431-4137

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASD 5 5/8" BORE TO 865'. THE PLUGGING PROPOSAL WAS TO PLACE A 300' CEMENT PLUG AT T.D., A 100' CEMENT PLUG AT 500', AND A CONTINUOUS CEMENT PLUG FROM 200' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: NONE
Date/Time Plugging Completed: 04/25/2005 6:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

TUBING WAS RAN INTO THE WELL TO T.D.. THE WELL WAS GELLED FOR BRIDGING PURPOSES. 60 SACKS OF CEMENT WERE PUMPE THROUGH THE TUBING TO T.D.. THE TUBING WAS PULLED TO 500' AND 20 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE TUBING WAS PULLED TO 200'. CEMENT WAS PUMPED INTO THE TUBING UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE TUBING WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED
KCC DISTRICT #3

APR ~~25~~²⁷ 2005 CPT

CHANUTE, KS

RECEIVED
MAY - 2 2005
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

INVOICED
DATE 5-2-05
INV. NO. 2005061510