

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-137-20434-00-00
Spot: N2SWNWSW Sec/Twnshp/Rge: 31-5S-21W
1850 feet from S Section Line, 330 feet from W Section Line
Lease Name: NORMAN Well #: 1
County: NORTON Total Vertical Depth: 3802 feet

Operator License No.: 9449
Op Name: GREAT EASTERN ENERGY & DEV. CO
Address: 550 W. TEXAS STE 660
MIDLAND, TX 79702

SURF Size: 8.625 feet: 262

#123⁶⁷

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/24/2005 6:30 AM
Plug Co. License No.: 9292 Plug Co. Name: SCHECK, TIMOTHY DBA SCHECK OIL OPERATION
Proposal Rcvd. from: DORAN MARKHEIM Company: SCHECK, TIMOTHY DBA SCHECK Phone: (785) 483-3404

Proposed Plugging Method: Order 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES WitnessType: NONE
Date/Time Plugging Completed: 04/24/2005 8:30 AM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 3766' w/25 sxs.
2nd. Plug at 1950' w/25 sxs.
3rd. Plug at 1125' w/100 sxs.
4th. Plug at 315' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

RECEIVED
MAY - 2 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed [Signature] (TECHNICIAN)

INVOICED
DATE 5-2-05
INV. NO. 2005061502

Form CP-2/3

APR 28 2005