

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-21429-00-00
Spot: NESWNE Sec/Twnshp/Rge: 4-25S-16W
1700 feet from N Section Line, 1650 feet from E Section Line
Lease Name: KOETT Well #: 2
County: EDWARDS Total Vertical Depth: 4603 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S. MAIN
STAFFORD, KS 67578

MSCC Size: feet: 2457 WITH 100 SX CMT
PROD Size: 5.5 feet: 4131 WITH 100 SX CMT
SURF Size: 8.625 feet: 248 WITH 200 SX CMT *\$14960*

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/19/2005 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK TO 3870' & 5 SX CMT ON TOP OF SAND BRIDGE. PULL PIPE. PLUG AT 1100' WITH 15 SX GEL PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/19/2005 2:30 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

ANHYDRITE 1060-1100'. SANDED TO 3870' & 5 SX CMT. 1ST PLUG PUMP THROUGH CASING @ 1100' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG PULL CASING TO 280' & PUMP 50 SX CMT. 3RD PLUG PULL CASING TO 40' & CIRCULATE CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
3969	3974		
3928	3934		

RECEIVED
MAY - 2 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2120' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Steve Durrant
(TECHNICIAN)

INVOICED
DATE 5.2.05
INV. NO. 2005061506