

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-145-20027-00-01  
Spot: NWSW Sec/Twnshp/Rge: 19-20S-20W  
1980 feet from S Section Line, 570 feet from W Section Line  
Lease Name: BELTZ Well #: 1  
County: PAWNEE Total Vertical Depth: 4400 feet

Operator License No.: 30742  
Op Name: PALOMINO PETROLEUM, INC.  
Address: 4924 SE 84TH STREET  
NEWTON, KS 67114

CIBP Size: feet: 3842  
PROD Size: 5.5 feet: 4400  
SURF Size: 8.625 feet: 333 WITH 235 SX CMT

\$143<sup>00</sup>

Well Type: SWD UIC Docket No: D14470.0 Date/Time to Plug: 05/03/2005 9:30 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: BILLY Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: PULL TUBING TO 1400' & SPOT 20 SX CMT. RUN BOND LOG. PRESSURE TEST CASING. CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT  
Date/Time Plugging Completed: 05/03/2005 4:00 PM

WitnessType: COMPLETE (100%)  
KCC Agent: MICHAEL MAIER

Actual Plugging Report:

FOUND FIBERGLASS FISH @ 3000'. PULLED TUBING TO 1400' & SPOT 20 SX COMMON CMT W/3% CC. PULLED TUBING & RAN BOND LOG FROM 1400' TO SURFACE. FOUND CMT ALL THE WAY UP. PRESSURED CASING TO 500# & HELD. RAN TUBING TO 1300' & USED 110 SX CMT TO CIRCULATE TO SURFACE. PULLED TUBING & TOPPED OFF WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4349	4355		
3610	3680		

RECEIVED  
MAY - 6 2005  
KCC WICHITA

Remarks: USED COMMON CMT W/3% CC & 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: TBG

District: 01

MAY - 4 2005  
MP

Signed Michael Maier  
(TECHNICIAN)

INVOICED

DATE 5-9-05

INV. NO. 2005061534

Form CP-215