

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21975-00-00
Spot: W2 Sec/Twnshp/Rge: 27-31S-31W
2640 feet from S Section Line, 1320 feet from W Section Line
Lease Name: UNRUH FRICKE A Well #: 1-27
County: SEWARD Total Vertical Depth: 5950 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 1321 W. 93 N.
VALLEY CENTER, KS 67147

SURF Size: 8.625 feet: 1709

\$193³⁸

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/28/2005 2:30 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: SKIP Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: 1ST PLUG AT 3100' WITH 100 SX CMT. 2ND PLUG AT 1720' WITH 50 SX CMT. 3RD PLUG AT 570' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE
Date/Time Plugging Completed: 03/28/2005 5:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG AT 3100' WITH 100 SX CMT. 2ND PLUG AT 1720' WITH 50 SX CMT. 3RD PLUG AT 570' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. NO MOUSE HOLE.


Perfs:

RECEIVED
APR 25
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

[Handwritten Signature]

(TECHNICIAN)

INVOICED

DATE

4.25.05

INV NO.

2005061452

Form CP-23