

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-30471-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 22-21S-12W
1047 feet from S Section Line, 2422 feet from E Section Line
Lease Name: ROSE Well #: 3
County: STAFFORD Total Vertical Depth: 3582 feet

Operator License No.: 5430
Op Name: ENERGY THREE, INC.
Address: 1437 OLD SQUARE RD #201A
JACKSON, MS 39211

PROD Size: 5.5 feet: 3582 WITH 100 SX CMT
SURF Size: 8.625 feet: 281 WITH 175 SX CMT

42
\$116

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/15/2005 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND BACK TO 3280' & PUT 5 SX CMT ON TOP OF SAND BRIDGE. RUN TUBING & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/15/2005 3:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND BACK TO 3280' & PUT 5 SX CMT ON TOP OF SAND BRIDGE. RUN 2 7/8" TUBING IN TO 660'. CIRCULATED 300 SX CMT FROM 660' TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
3466	3470		
3414	3420		
3386	3390		
3330	3334		

RECEIVED
APR 25 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY COPELAND. RECOVERED 360' OF 5 1/2" CASING (PARTED).

Plugged through: TBG

District: 01



Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED
DATE 4.25.05
INV. NO. 200506145.3

Form CP

