

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21756-00-00
Spot: SW Sec/Twnshp/Rge: 14-22S-33W
1320 feet from S Section Line, 1320 feet from W Section Line
Lease Name: BECKER Well #: 2-14
County: FINNEY Total Vertical Depth: 2770 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS, INC. OF KANSAS
Address: PO BOX 8647
WICHITA, KS 67208

PROD Size: 4.5 feet: 2766 WITH 475 SX CMT
SURF Size: 8.625 feet: 330 WITH 330 SX CMT

\$90⁰³

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/08/2005 10:00 AM
Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC
Proposal Rcvd. from: TIM THOMSON Company: OIL PRODUCERS Phone: (620) 482-2943

Proposed Plugging Method: PUMP 300# HULLS WITH 20 SX CMT. MUD SPACER TO 1400'. PUMP 110 SX CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/08/2005 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMPED 175 SX CMT DOWN 4 1/2" WITH 150# HULLS MIXED IN LEAD CEMENT. AFTER 4 HOURS CEMENT DROPPED TO 250'. PUMPED 30 SX CMT CLASS A NEAT CMT. TOP OFF 4 1/2" CASING. STAYED FULL. HOOK UP TO 4 1/2" X 8 5/8" ANNULUS. PRESSURE TO 1200 PSI. ANNULUS WAS FULL.

Perfs:


Top	Bot	Thru	Comments
2648	2654		
2601	2604		

RECEIVED
APR 25 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL & CLASS A CMT BY ACID SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Ken Jehlik
(TECHNICIAN)

INVOICED
DATE 4-25-05
NO. 200506458

Form CP-2/B