

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-19079-00-01  
Spot: NESWSW Sec/Twnshp/Rge: 20-11S-17W  
990 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: HADLEY J Well #: 2  
County: ELLIS Total Vertical Depth: 3901 feet

Operator License No.: 9449  
Op Name: GREAT EASTERN ENERGY & DEV. CO  
Address: 550 W. TEXAS STE 660  
MIDLAND, TX 79702

PROD Size: 5.5 feet: 3543  
SURF Size: 8.625 feet: 1157  
T1 Size: 2.875 feet: 3253 w/400 sxs cmt

#126<sup>78</sup>

Well Type: SWD UIC Docket No: D06756.0 Date/Time to Plug: 04/20/2005 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: BUTCH LAWHORN Company: GREAT EASTERN ENERGY & DEV. Phone: (785) 623-7520

Proposed Plugging Method: Ordered out 350 sxs cement - 3% cc.  
2 7/8" steel tubing set at 3253' w/400 sxs. T.O.C. 1210'- 05/06/2004.  
Ran 2 7/8" packer on 3/4" rods for MIT on 04/19/2005. Failed MIT.  
Fluid circulated out 5 1/2" casing annulus. Unable to release packer, backed off 3/4" rods at 1750'.  
Decided to P&A.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/20/2005 10:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

ELI Services perforated 4 holes at 1200'.  
Allied pumped 190 sxs common - 3% cc.  
Circulated cement out 5 1/2" casing. Shut in.  
Allied pumped 95 sxs common - 3% cc.  
Circulated cement out 8 5/8" x 5 1/2" annulus. Shut in.  
Squeezed with 65 sxs common - 3% cc.  
Max. P.S.I. 900#. S.I.P. 150#.

Perfs:

RECEIVED  
APR 22 2005  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

NO

Signed Richard Williams  
(TECHNICIAN)

INVOICED  
DATE 4.25.05  
INV. NO. 2005061455

APR 20 2005

20-11-17W


MURFIN, RAINS & WILLIAMSON #2      HADLEY 'J'      NE SW SW

Contr. MURFIN DRILLING CO      ELLIS      County

E 1909RB      Comm. 7-14-58      Comp. 8-1-58      IP S W D W

Tops	Depth	Datum	Casing
ANH	1147	762	8" 1158  DST 3419-75/1 HR, 15' MUD BHP 590#
HEEB	3093	-1184	
TOR	3115	-1206	
LANS	3137	-1228	
B/KC	3379	-1470	
GONG	3414	-1505	BEMIS-SHUTTS POOL
ARB	3494	-1585	
TD	3835	-1926	

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS



1909RB  
 HADLEY 'J'  
 NE SW SW