

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-22978-00-00
Spot: SENESE Sec/Twnshp/Rge: 17-22S-11W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: KLEPPER SE Well #: 6
County: STAFFORD Total Vertical Depth: 3670 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL, SUITE 100
WICHITA, KS 67206

PROD Size: 5.5 feet: 3660 WITH 150 SX CMT
SURF Size: 8.625 feet: 270 WITH 175 SX CMT

\$119²⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/19/2005 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 3470' & 5 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/19/2005 1:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 3470' & 5 SX CMT. SPOTTED PLUGS THROUGH THE CASING WHILE PULLING. 1ST PLUG @ 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3532	3538		

RECEIVED
APR 25 2005
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2410' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey
(TECHNICIAN)

INVOICED
DATE 4.25.05
INV. NO. 2005061457

Form C-2/3
[Signature]